



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.


We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

B 428155





TG
270
G21

Revised

W. H. H. H. H.

GRAPHICAL METHOD
FOR THE ANALYSIS OF
BRIDGE TRUSSES;

EXTENDED TO
CONTINUOUS GIRDERS AND DRAW SPANS.

BY
CHAS. E. ^{Greene} GREENE, A. M.,

PROF. OF CIVIL ENGINEERING, UNIVERSITY OF MICHIGAN.

ILLUSTRATED BY THREE FOLDING PLATES.

NEW YORK:
D. VAN NOSTRAND, Publisher,
23 MURRAY STREET AND 27 WARREN STREET.

1875.



Entered according to Act of Congress, in the year 1874, by

CHARLES E. GREENE,

in the Office of the Librarian of Congress, at Washington.



From the Library of
Prof. C.S. Denison
73-31

07-80-8171E44

CONTENTS.

	PAGE
INTRODUCTION.....	5
CHAPTER I.	
SINGLE SPAN TRUSSES, WITH HORIZONTAL CHORDS.....	7
CHAPTER II.	
SINGLE SPAN TRUSSES, WITH INCLINED CHORDS.....	24
CHAPTER III.	
CONTINUOUS GIRDER OF TWO SPANS.....	30
CHAPTER IV.	
CONTINUOUS GIRDER OF MANY SPANS.....	53
CHAPTER V.	
PIVOT BRIDGES OR DRAW SPANS... ..	58

INTRODUCTION.

While bridge trusses for single spans have been treated of very fully by many authors, and the interrelation of their parts is well understood, those engineers who have had occasion to investigate the subject are fully aware of the difficulties which beset the attempt to determine the stresses on trusses continuous over the piers and on pivot or drawbridges. The mathematical investigations are intricate, and the formulæ deduced are troublesome in application. Most of the authorities pass over one or both of these problems with a judicious silence, and only by dint of hard study, and a diligent brushing up of mathematics in which the best of engineers are liable to become rusty, can any one follow the very few writers who do touch upon these subjects.

Prof. Clerk-Maxwell has given us a graphical method which, when applied to roofs and trusses under a steady load, leaves nothing to be desired. We also possess a method for graphically finding the stresses on single trusses, which, with some modifications, is explained and illustrated in the first part of this work; but its

extension and adaptation to continuous girders and draw-spans, as subsequently set forth, is believed to be entirely original.

The method will be found to be general in its application, easily put upon paper and well adapted for the drawing table and practical work. The instruments required are simple :—a good drawing-board, triangles, T-square or straight-edge, scale and lead-pencil.

In order to make all the steps of the process perfectly plain, especially to those unacquainted with graphical methods in general, and perhaps at the risk of dwelling too long on well understood points, we have commenced with the triangle of forces, whence we can probably all start together, and then have taken up shearing force and bending moment in a beam or truss ; trusses of single span with horizontal chords, with inclined chords ; trusses of two continuous spans, of several spans ; and finally pivot or draw spans.

If the reader will draw some of the following diagrams for himself, on a much larger scale, he will more readily see the truth of the statements which will be made ; and if we succeed in removing some of the mystery which surrounds these latter classes of bridges, our object will be accomplished.

CHAPTER I.

SINGLE SPAN TRUSSES: WITH HORIZONTAL CHORDS.

1. We know, by one of the fundamental theorems of mechanics, that, if three forces, not parallel, act upon a body, and are balanced, their directions must intersect at a common point, and that these forces must be proportional to the sides of a triangle drawn parallel to their directions; and that, conversely, if three forces be taken parallel to the three sides of any triangle, and proportional in magnitude to the same sides, with the direction of the several forces taken in the order obtained by passing over the sides of the triangle in succession, these three forces, applied at one point, must balance or be in equilibrium.

If the weight W , Fig. 1, be hung from two points, A and B , by the cords AC and CB , we may find the pull or tension on each of the cords, by drawing a vertical line ab , equal, by any convenient scale, to the given weight W , and then drawing the lines ac and bc , from the extremities of ab , parallel to AC and BC , intersecting at c . Then will ac and bc represent, by the same scale by which W was laid off, the pull on the cords AC and BC . The arrows represent the directions of the stresses relatively to the point C , and the arrows on the triangle abc must

be found to point successively in order round the triangle.

If W and the two stresses ac and bc had been given, we might have reversed the problem, and found the direction and length of two cords which, while supporting W , would have exerted the given tensions on the points A and B . As it is possible to draw any number of triangles on the line ab , we may have a like number of arrangements of cords from A and B to carry W .

2. If we have several weights suspended from the points A and B , Fig. 2, by means of a cord whose weight may be neglected or considered to be included in the given weights, we find the tensions on the several portions of the cord by the successive applications of the above process. The weight at C is balanced by the tensions of AC and CD , and we may draw the triangle of forces for the point C . Next, having the weight W_2 and the tension, just found, on CD , we may draw a triangle for the point D .

But we may bring the triangles together, into one figure, by the following construction. Draw a vertical line 1-2, and measure on the same W_1 , W_2 , W_3 and W_4 , successively, to any convenient scale of pounds or tons to the inch. Draw 1-0 parallel to AC and 2-0 parallel to BF . Connect the point 0 with the other points of division on the vertical line. Then will $a-c$, $c-d$, $d-e$, $e-f$ and $f-b$ be equal to the stresses on AC , CD , DE , EF and FB , and the portions of the cord must be

parallel to the lines radiating from 0, or the cord will not otherwise be in equilibrium.

The figure 012 will be called the *stress diagram*, the line 1-2 the *load line*, and the cord from A to B, which hangs in what is called a *funicular polygon*, we shall have occasion hereafter to designate the *moment curve*.

If the weights and their horizontal distances from the point A and the horizontal distance of B from A were alone given, we might draw a *moment curve* to satisfy the condition of equilibrium, by assuming the point 0 in any convenient position, drawing the radiating lines to the several points on 1-2, then drawing a line parallel to $a-c$ from A to meet a vertical through W_1 , from the point C, so found, drawing a line parallel to $c-d$ to meet a vertical through W_2 , and so on, the last line, parallel to $f-b$, determining the position of B, since its horizontal distance from A was supposed given. This latter simple application of the method for finding a moment curve will suffice for the investigation which is to follow.

3. If all the forces act on a structure in one vertical plane, they may be resolved into horizontal and vertical components in that plane. The external forces considered here are all vertical, being the weights of the structure and the load, together with the reactions of the points of support which balance them. If a beam or truss, supported in any manner, is cut by a vertical plane, we shall have, on one side of the plane of section, the resultant of all the external vertical forces which act upon the portion

of the beam upon that side, and this resultant must be balanced by the sum of the vertical components of the stresses in that section of the beam, or by what is commonly called the *shearing stress*; and the resultant of vertical forces just spoken of is also called the *shearing force* at the section in question. Further, the external forces on one side of the plane of section, (since they are vertical, they have no horizontal components;) have *moments* around the plane of section, and the resultant moment, called the *bending moment*, is obtained by multiplying each force by its distance from the plane of section as a lever arm, adding together those products which have a tendency to rotate in one direction, and subtracting the sum of those products which tend to rotate in a contrary direction. The remainder is the bending moment at the section and tends to produce rotation in the direction shown by the larger sum. This moment is balanced by the *moment of resistance* of a couple made up of the respective resistances to compression and extension of the fibres or pieces in the two portions, upper and lower, of the beam or truss, multiplied by the distances between the sets of particles undergoing equal opposite stresses. Knowing the shearing force and bending moment at different sections of a beam or truss, we must have forces exerted, through the portion cut by the plane of section, sufficient to balance them.

4. Suppose now a beam, such as is represented in Fig. 3, to be supported at the two ends, and to have four un-

equal weights situated, as shown, at unequal intervals upon it. Let the weight of the beam be included in the imposed weights. It is required to find the *supporting forces*, or the pressures P_1 and P_2 , upon the abutments A and B, the shearing force and the bending moment at every point.

Draw a stress diagram, as before, by laying off, on a vertical line, 1-2, Fig. 3, the weights or loads W_1, W_2 , etc.; assume a point 0 at a convenient distance from 1-2, and draw radiating lines from 0 to all the points of division on 1-2. Draw vertical lines through the points of support and the loaded points, A, C, D, E, F and B. Commence at some point, A' , in the vertical through A, and draw $A'C'$ parallel to 0-1. From the point C' , where this line cuts the vertical through the first weight, draw $C'D'$ parallel to 0-3. Continue the same process until the last line $F'B'$, drawn parallel to 0-2, meets the vertical line let fall from B, the second point of support.

If $A'C'D'E'F'B'$ were a cord, fastened at A' and B' , and under the action of the given weights in their given positions, it would be in equilibrium, as shown in a preceding section. The pull on A' would be in the direction $A'C'$ and of the amount 0-1. The pull on B' would be in the direction $B'F'$ and of the amount 0-2. If now the two ends of the cord, in place of being fastened at A' and B' , were attached to the ends of a rigid bar, $A'B'$, the whole system might be suspended by two cords from the points A and B without disturbing the equilibrium of the

polygon. For, if we draw 0-5, in the stress diagram, parallel to $A'B'$, we can see that the inclined pulls at A' and B' are, by the introduction of the bar $A'B'$, each decomposed into a thrust along the bar and a force acting vertically downwards, as shown by the arrows. At the point A' we have three forces which, in the stress diagram, must make the triangle whose sides are 0-1, 0-5 and 1-5. In the same way, considering the point B' , we shall have, in the stress diagram, the triangle whose sides are 0-2, 0-5 and 2-5. The thrust 5-0 from A' balances the thrust 0-5 from B' , and there remain 1-5 and 5-2, or P_1 and P_2 , the forces exerted by this system on the points of support A and B . Any other system of framing, loaded in the same way, must give the same pressure on the points of support, and the reactions of the abutments will be equal and opposite to these pressures.

Therefore, to find the supporting forces :—having drawn the moment curve, connect A' with B' , draw 0-5 parallel through 0, and the two portions into which the load line is thus divided will be the forces required.

5. As the shearing force at any section is the resultant of the vertical forces on one side of the plane of section, the shearing force at any point between A and C will be P_1 , the only vertical force acting on the left of that point. As P_1 , the reaction of the abutment, acts in an upward direction, draw A_g vertically, equal to P_1 . Between C and D the shearing force will be $P_1 - W_1$, or 3-5; between D and E it will be $P_1 - W_1 - W_2$, or 4-5; and so

for all parts of the beam. The shearing forces can be read off directly from the load line, as just shown, the point 5 being always one end.

But, if we draw from g a line gi , parallel to AB , then at the point i , vertically over C , measure off, downwards, ik , equal to W_1 , draw kl horizontally, then lm , equal to W_2 , and then $mnpqrs$, we shall have a broken line, the ordinate to which, from any point of the beam AB , will be the shearing force at that point. When the W 's which have been subtracted exceed P_1 , the broken line passes below AB , and finally, on arriving at B , having subtracted all the W 's, we have a shearing force equal but opposite to P_2 . So, at any section, the shearing force at one side of the plane of section, obtained by the subtraction just described, will always be equal and opposite to the shearing force on the other side of the same plane of section, obtained by working from B , with the supporting force P_2 as the minuend. Such a result is required, to fulfil the condition of equilibrium.

6. Lastly, to find graphically the bending moment at any point. Take the point S . The bending moment on the beam at S is

$$P_1 \cdot AS - W_1 \cdot CS - W_2 \cdot DS.$$

Drop a perpendicular from S , cutting the polygon $A'E'B'$ at I and K . Produce $A'C'$ and $C'D'$ to meet this perpendicular at L and M . Also draw $C'N$ horizontally. In the stress diagram draw a horizontal line $0-6$,

through 0, to meet the load line. Call this line H. It is the horizontal projection of the stress on each side of the funicular polygon, or moment curve, and is plainly equal to the horizontal stress at any point of the curve, which is well known to be *constant* for a system of vertical loads.

The triangles C' N M and 061, having their sides parallel, are similar, and we have the proportion

$$M N : C' N = 1.6 : 0.6.$$

From the similar triangles C' L N and 036 we have

$$L N : C' N = 6.3 : 0.6.$$

Hence

$$\frac{M N - L N}{C' N} = \frac{(1.6) - (6.3)}{0.6},$$

or

$$M L \cdot (0.6) = (1.3) \cdot C' N.$$

But

$$0.6 = H; \quad 1.3 = W_1, \therefore \\ H \cdot M L = W_1 \cdot C' N = W_1 \cdot C S.$$

In the same way

$H \cdot L K = W_2 \cdot D S$, and $H \cdot I M = P_1 \cdot A S$; \therefore
the bending moment

$$M = H (I M - M L - L K) = H \cdot I K.$$

Hence the bending moment, at any point of the beam, is proportional to the ordinate, from A' B' to the moment curve, vertically below that point, and is equal to the product of that ordinate by H, the constant horizontal component of the tensions on the curve.

The ordinate must be measured by the scale to which the beam is drawn, and the line which represents H by the scale to which the load line is measured off; but the two figures may be of the same scale, that is number of tons and feet to the inch, or of different scales, whichever is most convenient. If the point 0 be taken at such a distance from the load line that 0-6 shall measure just ten or one hundred units of weight in length, the bending moment will be readily obtained by scaling the ordinate, and moving the decimal point to the right, one or two places as the case may be.

It will be noticed, that the greatest value of the shearing force occurs where the bending moment is least, and *vice versa*.

7. We may now proceed to apply this method to a bridge truss, with parallel chords, under a given moving load. Let the truss be represented by A B C D, Fig. 4, supported at A and D. The span is supposed to be 80 feet, height of truss 10 feet, fixed load $\frac{1}{4}$ ton per running foot, moving load $\frac{1}{2}$ ton per running foot. The scales of the figure are, as shown below it, 30 feet = 1 inch, and 30 tons = 1 inch. The small weights represent the fixed load, arising from the truss and platform, as if concentrated on the joints of the lower chord; the larger weights represent the moving load. As each panel is ten feet long, the load from the truss at each joint will be $2\frac{1}{2}$ tons, and from the rolling load 5 tons. The points A and D will each carry one half a panel weight; these weights will cause no stress in the truss, and might be neglected

altogether ; but it will be found convenient to plot them on the load line, as thus the total weight of the truss will be accounted for, and the shearing force will be more readily obtained.

Suppose the rolling load to extend from the abutment A to the joint J, inclusive. Draw a vertical line, and lay off 1-2 equal to $\frac{2\frac{1}{2} + 5}{2}$ tons, the weight at A ; next 2-3 = $7\frac{1}{2}$ tons at E, 3-4 = $7\frac{1}{2}$ tons at F, and so on to 6-7 at J ; then 7-11 = $2\frac{1}{2}$ tons at K, 11-12 = $2\frac{1}{2}$ tons at L, and finally $1\frac{1}{4}$ tons at D, reaching a point 13, midway between 12 and 14. Next assume the point 0, which is here taken so that H measures 20 tons. Leave out of consideration 1-2, the weight at A, and starting at A', a convenient distance vertically below A, draw A' E', E' F', L' D', parallel respectively to 2-0, 3-0, 4-0, &c., the line L' D' being drawn parallel to 12-0.

Connect A' D', and draw, in the stress diagram, 0-9 parallel to A' D'; 1-9 and 9-13 will be the supporting forces at A and D. Lay off vertically, from a line $a d$, $d g$ equal to 9-13, and $a n$ equal to 1-9. The shearing force at any section might then be represented by a broken line, as in Fig. 3, $g i k l m$, &c. ; but we can more readily draw the line $g p n$, which would be the bounding line of all the shearing ordinates, in case the load were uniformly distributed, instead of being concentrated at a series of points. If we wished to draw the broken line, we should deduct from $d g$ the load on D, and then draw a horizontal line across the space under the first panel, which line would cut $g p$ at a point vertically above g , or in the

middle of a panel space. That this ought to occur may be seen, if we consider that the load on each joint comes from half of the panel on each side. The inclination of gp must be such, that the ordinates to it shall diminish $2\frac{1}{2}$ tons for each panel; the ordinates of pn must also diminish at the rate of $7\frac{1}{2}$ tons per panel; and, if gp and pn are drawn from g and n respectively, then p will come in the middle of a panel.

8. If the rolling load retires, so that G is the last fully loaded point, we shall have three loads of $7\frac{1}{2}$ tons each, and the points from I to L will carry only $2\frac{1}{2}$ tons each. We may make available a large portion of the curve already drawn; since 4-5 represents the load on G , we can lay off the smaller loads below, the one on L falling at 6-16. Constructing a second moment curve, as we did the first, we shall get $A' E' F' G' I' J'_2 K'_2 L'_2 D'_2$, and, drawing 0-8 parallel to $A' D'_2$, we get the new supporting forces for this position of the rolling load. Hence we find $h r$ and $r i$ as we did gp and pn .

If the load extends over the whole truss, our load line will be 1-10, and the moment curve $A' E' F' G' I' J' K' L' D'$. As 0 was taken opposite the middle of 1-10, and as, for an entire uniform load, the two supporting forces are equal, the line $A' D'$ is horizontal. The shear diagram for this case is $d c v b a$.

9. If we should carry out the construction for every position of the load, we should discover some facts which are of importance as rendering needless the drawing of

so many diagrams; and we may see indications which lead to that discovery in the figure already described. First:—the bending moment, at any point of a beam or truss, is greatest when the whole beam is loaded. The curve $A'G'J'D'$ will give ordinates of the greatest length, and these ordinates, multiplied by H , give the bending moments. Second:—the shearing force at any point is greatest when the longer segment, of the two into which the point divides the truss, is fully loaded. For example, the shear in the panel JK is greatest when the rolling load extends from A to J , at which time the ordinate will rise to p ; but, for any other position of the load, the ordinate will be less.

Third:—we should find, in addition, that the points p , r , &c., lie on a parabola whose tangents are readily drawn; and the curve shown by the dotted line from m to t , can then be constructed.

The limiting values of the shearing force at the abutments are, for the least value, *one half of the weight of the truss unloaded*, and, for the greatest, *one half of the weight of the truss and full load*. Lay off ae equal to the former amount and dc equal to the latter. If dc be plotted above ad , ae must be plotted below; connect e and c with the middle point v of ad . Otherwise, the shearing diagram for the loaded truss will be $dcba$, and for the unloaded truss $dfea$; all other diagrams must have their terminal points between f and c , and e and b ; we have, then, the tangents cv and ev on which to construct the parabola.

10. The curve is easily found as follows:—let AB and BC , Fig. 5, be two tangents. Divide each tangent into the same number of equal parts; number the points of division 1, 2, 3, &c., as shown. Draw straight lines 1-1, 2-2, 3-3, &c., and the curve sketched tangent to these lines will be the parabola required. In Fig. 4, each tangent is already divided by the verticals into four equal parts; if each part be now bisected, a sufficient number of points will be obtained, and the lines then drawn will limit the ordinates without sketching in the curve. The ordinates in the end panels will thus terminate at m and t , the middle points of the panels, (as required by § 7, end).

11. The shearing force in any panel is then obtained, for example in the panel KL , by erecting the ordinate ls to the curve, at the middle point l of the panel length. The stress on the tie SK is then easily obtained by drawing sk , parallel to SK , from s until it meets the horizontal line at k . The stress on the diagonal will be sl , and on the post SL it will be sl , to the same scale as cd or ae , and so for the other panels. The point r under the middle of the panel GI , will be the last one where we shall find any shearing force in an upward direction on the right hand side of the plane of section, when the load extends from A to G and in the panel GI is therefore found the last necessary tie parallel to CL .* The remain

*Many engineers carry the diagonals sloping one way through all of the panels, for practical reasons. But they are not essential beyond the point shown, and, as they do no real work, may be made as small as is thought desirable.

ing panel from G to A would require diagonals, if the sloping in the contrary direction, and as when the load goes off in the other direction we shall get similar but reverse stresses in these panels, exactly such as we have found from D to G . It is sufficient to find the stresses from D to G , and then make the truss from A to J symmetrical with D to G . The heavier the rolling load compared with the fixed load, the further will the diagonals sloping one way pass beyond the centre.

If a diagonal slants up towards the abutment to which its stress goes, it is a tie; if it slants down, it is a strut. If the load were placed on the top chord, the ordinate xl would be the stress on RK . In short, from any ordinate to the parabola at the middle of a panel, we determine the stress on that diagonal and vertical which, taken together, may be considered to connect two adjacent weights.

12. It is also unnecessary to draw any moment curve besides $A'F'I'K'D'$. The bending moment on the truss is taken at each panel joint. If we pass a plane of section, for example one through the joint K , we shall have, taking moments on the right of and about K , the thrust on the top chord in the panel RS , multiplied by the height of the truss RK , as the moment of resistance to balance the bending moment produced by the external forces. As the vertical RK and the diagonal SK both terminate at the proposed moment point or axis K , the stresses along those pieces cause no moments. Similarly,

taking moments round R, we have the tension on J K, multiplied by R K, to balance the bending moment. Therefore the compression on R S equals the tension on J K, and the same equality is true of S C and K L, and of all the other portions of the chords. Of course the compression or tension is constant for a panel length. There is no stress on L D or A E, as these pieces are unnecessary for equilibrium. The compression on the two panels of the top chord at the middle does not call for any equal tension on a panel length in the bottom chord, for the two ties which meet at I act directly against each other.

Now, as the maxima stresses on the chords occur when the entire span is loaded, to find the tension and compression on the bottom and top chords between any two adjacent diagonals which incline the same way, it is only necessary to take the ordinate to the parabola under the common panel joint of the two diagonals, multiply it by H from the stress diagram and divide by the height of the truss; the result will be the required tension and compression.

13. As we may draw the shearing diagram required for the solution of this case without employing a stress diagram, we may also draw the moment curve alone; or better, if the truss has parallel chords, as now supposed, we may draw a curve whose ordinates shall give directly the required tensions and compressions. For, H and the height of the truss being constant, these forces are direct-

ly proportional to the bending moment M . Call the span l , and the height of the truss k . It is well known that the bending moment at the centre of a beam supported at both ends, and uniformly loaded with a total weight (of truss and load), W , is

$$M = \frac{Wl}{8}.$$

Therefore the stress required at the centre will be $\frac{Wl}{8k}$.

As the bending moment varies as the ordinates to a parabola, so will the value for the chord stress vary. Therefore compute the ordinate for the middle point of the truss

$$\frac{Wl}{8k},$$

and, through the point thus found and the two ends of the diameter of length l , draw a parabola. To readily construct the required curve, (see Fig. 5,) taking DE equal to l , at the middle point G lay off GF equal to $\frac{Wl}{8k}$. Draw verticals through the panel joints, $DHIK$. Lay off $DS = GF$, and divide it into the same number of equal parts with DG . Draw FO , LP , MR and ND . Complete the other half of the figure, if thought desirable, in the same way. The points F , L , M , N and D will lie on the curve, and the stresses on the chords will be, in succession from the abutments to the middle, HN , IM , KL and GF .

Each part of the truss which undergoes tensile stress should have its effective section in square inches equal to

the maximum stress it must exert divided by the safe working stress on the square inch. The cross-section of pieces in compression should be determined by Gordon's Formula or some similar method. The working out of details does not come within the scope of these pages.

CHAPTER II.

SINGLE SPAN TRUSSES:—WITH INCLINED CHORDS.

14. While the determination of the stresses in a truss with chords which are inclined or curved is not quite so simple, it involves no particular difficulty, the chords being considered as jointed at each intersection. Take, for example, the truss represented by A B C D, Fig. 6. The span and the load are taken the same as those for the truss, Fig. 4, just described. The bending moment is obtained as before for the truss loaded throughout its length, and the stress diagrams of Fig. 4 apply to this case also. The bending moment at any panel joint, being obtained from the proper ordinate of the curve A' F' I' K' D' multiplied by H, must be divided by the height of the truss at the panel joint in question, and we shall then have the *horizontal component* of the pull or thrust on the chord. Multiply this horizontal component by the length of the inclined chord in the panel and divide by the horizontal distance between the panel joints; or, if we call the length, horizontally, of a panel a , and the difference of level of the two joints in the same chord b , multiply the horizontal component above by

$$\sqrt{1 + \frac{b^2}{a^2}},$$

and we shall have the stress on that piece of the chord.

15. To find the stress on any diagonal, such as OP , with the load as sketched in the figure, covering O for the last point, we must draw the moment curve $A'F'I'K'D_1'$, Fig. 4. Then consider that a plane of section has been passed through the panel $ONPQ$, Fig. 6. An enlarged view of this panel is drawn just below on the left. On one side of this plane, say the right hand, we have the vertical shearing force, the horizontal pull through Q and the horizontal compression which would act through N . On the other side of the plane we find three inclined pieces whose stresses must balance the rectangular components on the first side.

Now, from the moment curve for the given position of load, Fig. 4, take NJ' , multiply by H , divide by ON , and lay off the quotient, which is the *horizontal* stress through N , horizontally at vy .* In the same way $PK' \cdot H$, divided by PQ , gives us the horizontal stress through Q , laid off at vx . The vertical shearing force will be the ordinate to p , Fig. 4, and is plotted vertically upwards at vu . Now draw np from u , parallel to NP , and limit it by a vertical from y ; draw oq from v , parallel to OQ , till it meets the vertical through x ; draw the line op , and it must be parallel to OP , or some error in construction has been made. Thus we have a check on the accuracy of our work. By dispensing with this check it is only necessary to determine one of the horizontal stresses, and

* Diagrams I. to IV. of Fig. 6, are enlarged one and one-half times as compared with the lines obtained from Fig. 4, as shown by the attached scales.

then we may draw the other lines parallel to the respective pieces. Indeed it would be possible, by determining both of the horizontal stresses, to dispense with the shearing diagram altogether; but it would not be advisable so to do. The required stress on OP is op . The stresses on np , po and oq must follow one another round the figure, as shown by the arrows, which represent the actions of the pieces against the plane of section, as shown in the enlarged sketch of this panel, and it will be noticed that the horizontal projections of np , po and oq balance; while their vertical projections are in equilibrium with the shear vu .

16. It remains to find the stress on PQ . Consider the joint P . This joint is in equilibrium under the action of four forces exerted by the four pieces which meet at that point. These forces must form a closed polygon, and, as we have already determined two sides, the remaining ones are readily drawn. The stresses on NP and OP being represented by np and op , draw pq parallel to PQ and pr parallel to PR . The required stress on PQ is pq . The arrows in this quadrilateral show the direction of the stresses exerted on P by the several pieces, and they must proceed in order round the figure. The horizontal projection of the stress on PR is the same as that of the stress on OQ , which result would be expected. The stresses np , pr and oq are the ones existing in the pieces to which they refer for the present load; but, as they are not the greatest stresses which the chord pieces

undergo, they are of no special value here. The maxima stresses were determined in § 14.

17. The portion of the figure within the triangle $t d y$ gives a graphical method for finding the horizontal components $v x$ and $v y$ without calculation. For example : since

$$v y = \frac{N J' \cdot H}{O N},$$

draw $t d$ at any convenient angle with the horizontal line, make $t v = H$; $t b = O N$; $b d = N J'$ (Fig. 4) ; draw $b v$, and, parallel to $b v$, through d draw $d y$; $v y$ will be the required component. For, from similar triangles,

$$t b : H = b d : v y = \frac{b d \cdot H}{t b}.$$

Similarly, $t a = P Q$; $a c = P K'$ (Fig. 4) ; and $c x$, drawn parallel to $a v$, determines $v x$. If $c x$ and $d y$ cut the horizontal line at favorable angles, the values of $v x$ and $v y$ may be thus obtained quite satisfactorily.

18. If the moving load only extends to and includes $J K$, we construct, in the same way, diagram II., using the ordinates $R G'$ and $M' I'$ from Fig. 4. In this case $k m$ runs below the horizontal line, but the remainder of the figure is similar to the one just described. It will be noticed that the inclinations of the chord pieces $J L$ and $K M$ now act to increase the vertical force transmitted *towards* the abutment D . The stress on any diagonal is *increased* by such an inclination of either chord as tends to make the *height* of the panel, on the *side* of the abutment

toward which the diagonal conveys its load, *greater* ; and *vice versa*.

After we pass the point where the parabola for shear, Fig. 4, passes below the horizontal line, the vertical for shearing force must be drawn *down* from the horizontal line in Fig. 6. Then, taking the panel G J K I, and using the dotted curve of Fig. 4, we draw gj , ik , and ij , diagram III., exactly as before. Since gj and ik cross, we still have a pull on the diagonal I J, as shown by the arrows ; and we may also find a compression on J K, in case the inclination of J L does not take all of the remaining vertical force. An inspection of diagram III. will render this statement clear. If we advance one panel nearer abutment A, the moving load now being considered to rest on A and F only, the panel F E G I will give us diagram IV. On attempting to find the stress on a diagonal from F to G, we shall see, by the necessary direction of the arrow on fg , that a piece F G would thrust against the plane of section. As our diagonals are, in this example, supposed to be ties, we have passed the limit where those sloping in this direction are required. A similar set, from A to Q, will complete the truss. If the truss is deeper at the centre than at the ends, the effect of the inclination of the chords is to require more diagonals sloping one way than a truss with parallel chords will need. A bowstring girder, jointed at panel points, requires diagonals throughout.

19. The stress on any diagonal, such as O P, will be

found to be a maximum when the load extends from the abutment A to the panel joint at its foot, as has been previously stated to be the case with a truss having parallel chords. If the diagonals had been struts instead of ties, no difficulty would have been experienced ; the line op which now slants one way would in that case have slanted in the opposite direction. If the load were on the top chord, instead of the bottom as here, in place of finding the stresses on OP and PQ , we should find them on OP and ON ; that is :—take the vertical which meets the unloaded end of the diagonal in action. The change in diagram I. would be that, instead of drawing pr and pq , we should prolong oq (shown by a dotted line,) to meet the vertical through y , and the upper intercepted portion of this vertical would be the stress on ON .

By the method here given, of drawing the horizontal stresses on the right of the vertical line for shearing force, when the latter acts upward we have the stresses on the top and bottom chords in the relative positions of the pieces themselves, that is np is over oq . The bending moment tends to produce convexity downwards. We shall, in the latter part of the book, have occasion to refer again to these diagrams ; the bending moment in that case being in the contrary direction, we shall then plot the horizontal stresses to the left of the vertical uv .

CHAPTER III.

CONTINUOUS GIRDER OF TWO SPANS.

20. Let us pass next to the case of a beam supported at two points, loaded at intervals, and overhanging one of the points of support. Let A I, Fig. 7, be the beam, supported at A and B, and let the weight of the beam be considered as concentrated with the additional loads. Draw the stress diagram 012, as in other cases. Commence at A', and draw A' C' D' E' F' G' I' parallel to the radiating lines of the stress diagram, the angles occurring on the verticals let fall from the *weights*. There will be one line, parallel to 0-2, still to be added, and this line should be drawn from I' to the vertical through B, as in former cases, but to B', in the reverse direction. (Compare Fig. 3.) Connect A' B' and the moment diagram is complete. A line through 0, parallel to A' B', will divide the load line into the two supporting forces, P_1 at A and P_2 at B.

If we lay off P_1 at A, equal to A a, and then construct a c d e, etc., as was done in Fig. 3, we shall reach a point b under B; now, commencing at I, lay off I i equal to the weight at I, then add the weight at G, finally reaching the point b'. B b + B b' must be equal and opposite to P_2 , which acts upward. Drawing the horizontal line marked H through 0, we find the bending moment at any point by multiplying H by the ordinate between the moment curve

and the line $A'B'$ or $B'I'$ for that point. At K' , there being no ordinate, the product is zero ; consequently the beam is not bent at K . As we pass from K' to B' and I' , the ordinate, being below the curve, may be called negative ; the bending moment is in the contrary direction over the portion KI , from that existing over AK , and it tends to produce convexity on the upper side of the beam, reversing the tension and compression on the fibres. The point K is called a *point of contra-flexure*. The curvature of the beam is shown, to an exaggerated scale, by the dotted line $ALBM$.

In case the beam overhangs both points of support we may have two points of contra-flexure ; but the overhanging portions may have sufficient weight to cause convexity upwards over all the intermediate portion, when the line corresponding to $A'B'$ will pass entirely below the curve and there will be no points of contra-flexure. If the two points of support are brought together into one point, and the two overhanging portions balance each other, we have the case of a pivot or swing bridge when open. This case will be further considered in the sequel.

21. If we next turn our attention to a girder continuous over two spans, the simplest case of which is a beam resting on three supports, we shall find that a partial solution of the problem by mathematical calculation is attended with considerable difficulty, and that a complete solution for the bending moment and shearing force at every section, under moving, partial and irregular loads, taxes the

powers of the best mathematicians and is well nigh impossible, on account of the complexity of the formulæ, so far as any practical application of them by the engineer is concerned. Where each span has a uniform load over its whole extent, although different spans may have loads of the same or different intensities, Clapeyron's "Formula of the Three Moments" will readily give us the moments over the piers for a continuous girder, and hence we can obtain the moments at other points; and, if the beams are symmetrically loaded, or so loaded as to be horizontal over the piers, the investigations are not difficult and can be found in most text-books treating of the flexure of beams. But no book in common use gives us any method for determining the shearing stress under a partial load, a determination which is necessary before the bracing can be correctly proportioned.

We propose now to develop a graphical method which will be readily applicable to all cases of continuous girders, under discontinuous and moving loads, and by which we can as easily determine the maxima stresses on the chords and bracing of any truss, loaded in any manner, as we have done for single spans in the preceding pages. The diagrams will show, what might have been expected from analogy, that the maxima stresses on the chords of continuous girders occur when one or more spans are fully loaded, and the maximum stress on a brace occurs when the moving load covers one of the segments into which the piece under consideration divides the span; but, in both cases, the stresses in one span are very materially altered

by the presence or absence of a load on the adjacent spans.

22. Suppose that we have a beam, as represented in Fig. 10, supported on two abutments, A and C, and divided by the pier at B into two unequal spans. Its own weight is uniformly distributed, and it carries, in addition, a uniformly distributed load of twice the intensity from C to D and also from E to F. Divide the two spans into convenient parts, equal or unequal (here taken equal), and consider the load to be concentrated at the points of division. Draw verticals through these points, and, having constructed the load line and stress diagram 012, draw the moment curve between C' and A', as in previous examples. The loads at A and C are neglected, and are represented by the portions of the load line which project at 1 and 2; since B carries a load, the vertical through B will determine one of the angles of the moment line, in the same way as any other loaded point.

To complete the construction we must draw A' B' and C' B'. We know that B' must lie below the curve (for we have a negative moment of flexure over B), and we usually have two points of contra-flexure, where A' B' and C' B' cut the curve. We must have, further, some condition to limit the position of B', since there is manifestly but one correct value for the moment of flexure over the pier for a given position of the load. As no bending moment exists at A, A' B' must start from A'; and, similarly, C' B' is drawn through C'.

23. From the bending moment there arises in the beam a change of inclination at successive points, and a deflection, either *positive* or *negative*, of all portions of the beam from the original horizontal line. For the bending moment at any point, being opposed by the moment of resistance of the beam, causes an elongation and compression of the fibres on opposite sides of the beam, proportional to the bending moment. This elongation and compression causes (see Fig. 8) a change of direction of the centre line of the beam, in a vertical plane, at that point. Therefore the change of direction or inclination at any point is proportional to the bending moment at that point, or to the ordinate between the moment curve and the straight line, (as A' B', Fig. 10), and the total change of inclination between any two points is proportional to the sum of all the bending moments between those points, or to the area included between the *moment curve*, the straight line from the abutment to the pier and the two limiting ordinates under the points.

By reference to Fig. 8, we can see the change of inclination produced in the beam at A, by the elongation of the upper fibres at that point and the compression of the lower ones. We can also see the effect of successive changes of inclination, at B, C and D, in altering the direction of the beam, and we must note that the changes of inclination at E, F, &c., produced by bending moments in the opposite direction, tend to bring the beam back towards its original *direction*. Consequently, the change of inclination between any two points is proportional to the

algebraic sum of all the ordinates to the moment curve between those points; and, in Fig. 10, supposing $C' B'$ and $B' A'$ to be correctly placed, if we cut off an area from G' towards B' , equal to the area between A' and G' , the centre line of the beam, at the point vertically over the dividing ordinate just drawn, will have its tangent parallel to the tangent at A . If we know any point where the beam is horizontal, we can thus find the other points where it is horizontal; but the determination of this question is not material to our problem.

24. The *deflection* of any point of a beam from the original line depends upon the changes of inclination and the distances of the points at which they occur from the first point. Thus, if the originally straight stick ag , Fig. 9, is bent at a , the point g will be carried to a point on the line al , the distance through which it is displaced depending upon the angle at a and the distance ag ; if another angle is made at b , the point g will now be found on bi , and, on a further bending at c , it will move to the direction ch . The changes of inclination at d , e and f , in the contrary direction, will carry the point which was originally at g , through dk , em , fg , finally back again to g . (The deflections of all beams and trusses are so small that the curved line of a beam under a load is always considered practically equal in length to the horizontal distance between the two points of support.)

We see, then, that the position of a point D , Fig. 10, in a beam under flexure, in reference to some point, such as



C, as origin, and from a tangent to the beam through that origin, depends upon the successive changes of inclination between the two points and the distances from the point D at which they occur, regard being paid to the direction of the change of inclination. Then, as each change of inclination is proportional to the ordinate to the moment curve, the deflection of a point from a tangent through the origin is proportional to the sum of the products of each ordinate into its distance from the point in question; or, as the horizontal distances are the proportional projections of the distances on the tangent, and as the sum of each ordinate multiplied by its horizontal distance from D is the same thing as the area between C' and D' multiplied by the distance of its centre of gravity horizontally from D', *the deflection of D from the tangent through C is proportional to the area C' D' multiplied by the horizontal distance of its centre of gravity from the vertical through D.* Then, if CL is the tangent through C, the deflections of the points B and A, with reference to C, will be proportional to BK and AL, or, from the similarity of triangles, to BC and AC, two known quantities.

25. Therefore the two lines A'B' and C'B' must be drawn to a point B', so situated that (denoting the centres of gravity of the respective areas by a, b, c and d), the areas

$$\frac{C'P'D' \cdot de - K'D'B' \cdot ci}{C'P'D' \cdot df - K'D'B' \cdot ch - K'B'G' \cdot bh + A'F'G' \cdot ag} = \frac{BC}{AC}$$

All of these quantities are readily measured and com-

puted, as will soon be shown ; therefore we may draw $A' B'$ and $C' B'$ as trial lines, as near the right position as we can, and then compute the first ratio. If it does not equal the second ratio, move B' and try again ; a second approximation will generally be sufficient. Call any area, as above, multiplied by its distance from a certain point, an *area moment*.

We may, with advantage, modify a little the application of our method, and so obtain a rule more easily remembered and used. Draw the tangent $M B N$ to the beam at B . It is evident that $N C : M A = B C : B A$. Then, from the preceding reasoning, make

$$\frac{\text{area } C' P' D' \cdot dl - K' D' B' \cdot ck}{\text{area } K' B' G' \cdot bh - A' F' G' \cdot ag} = \frac{B' C}{B A}.$$

The deflection $M A$ being on the opposite side of the tangent from $N C$, the similar areas in the above proportion are taken with the opposite signs ; that is, $K' D' B'$ being taken minus in the first term, $K' B' G'$ is taken plus in the second, and so of the others. Or we may consider the distances to the right of B plus, and those to the left minus.

It is evident that there is but one position of B' which will satisfy the condition ; for, if B' is carried still further below K' , the first term of the proportion is diminished and the second term is increased, while, if B' is raised, the reverse takes place.

26. Another demonstration of the above theorem, which

is brief and which may be more satisfactory to some mathematical minds, is as follows :—

Let M denote the bending moment at any point of a beam, supported in any way ; let E denote the modulus of elasticity of the material and I the moment of inertia of the cross-section. Let the originally straight horizontal line of the beam be the axis of x , and let y be measured vertically. M will be a function of x . Let r = radius of curvature at any point. Then we may write the well-known equation for the curvature

$$\frac{1}{r} = \frac{d^2y}{dx^2} = \frac{M}{EI}.$$

If we integrate this expression once, considering I constant, we have

$$\frac{dy}{dx} = \frac{1}{EI} \int M dx = \tan. \text{ inclin.} = \text{inclination when small.}$$

If we could determine the constant of integration, we could find the inclination of the beam to the horizon at each point. But, if we integrate from 0 to x , the origin being taken at one of the points of support, say C , Fig. 10, we get a complete integral,—the area included between the moment curve and the straight line,—but one expressing only the change of inclination from the inclination already existing at C , or the inclination of the tangent at any point to the line CL .

Integrating again, we have

$$y = \frac{1}{EI} \iint M dx^2 = \text{deflection.}$$

This integral is a volume, and, taken between limits as before, is the summation of each area from 0 to x , into a height dx , giving a cone with a base $= \int_0^x M dx$ and a height x ; or it is otherwise equal to the area $\int M dx$ multiplied by the distance of its centre of gravity from the point whose abscissa is x . I is here considered constant, and may be so taken in most trusses. If I varies, it will be expressed in terms of x and introduced within the integral sign.

27. The areas are readily measured by scaling the successive ordinates and multiplying by the constant distance between two ordinates, as is done in calculating the contents of any irregular area by offsets. If the verticals are not too far apart, the areas are practically parabolic segments, triangles, and combinations of the two. The centre of gravity of a parabolic segment, such as $C'D'P'$, is at d , half way horizontally between C' and D' . The centre of gravity of any triangle whose base is vertical, is on a vertical line one-third of the horizontal distance from the base to the vertex. If we connect G' and K' by a straight line, the area $G'K'B'$ will be found to be the difference between a triangle and a parabolic segment, and the moments of these areas about $A'h$ may be computed separately. Similarly, if an area is partly bounded by portions of two different parabolas, the common point of the two parabolas may be connected with the extreme points of the area, and it will be thus divided into a triangle and two parabolic segments. It may be unnecessary

to remark that any area may be divided into a number of parts, the respective centres of gravity found, and then the area moments of these parts calculated and combined, with the same result as if the area had been treated as a whole.

28. If the two spans are equal the *ratio* of the *area moments* becomes an *equality*.

When we have finally determined the position of A' B' and C' B' for the given load and distribution of the same, we have, as in single spans, the bending moment at each point by taking the proper ordinate and multiplying by H from the stress diagram. Now, upon drawing from 0 two lines, 04 and 05, parallel to B' C' and A' B', we shall divide the load line into three portions which are : 1-4 the supporting force at C, 4-5 the supporting force at B, and 5-2 the supporting force at A. The beam, as now loaded, has two points of contra-flexure, at D and G. It may happen that, when one of the spans is much longer and more heavily loaded than the other, the point of contra-flexure, G', on the shorter span, moving towards the outer end, may finally pass off altogether. As G' moves towards A', the point 5 will approach 3, and, when G' reaches A' and disappears, 5 will pass beyond 3. There will still be some slight pressure on the abutment, although the span A B will be convex upward throughout its whole extent ; and the end of the beam will not rise from the abutment A until it is found necessary, in order to satisfy the condition of proportionality of *area moments*, to

so draw $A'B'$ that its parallel, 0-5, passes entirely outside of the end 2 of the load line. As soon as this occurs, the beam must be treated as one resting on two supports and overhanging at one end, § 20, Fig. 7.

Finally, lay off P_1 and P_2 , at mn and ts , draw the inclined lines, as was done in Fig. 4, steeper where the load is more intense, and, finding that $p q + p r = P_2$, we know that our shear diagram is complete.* Then the ordinates between mt and the lines just drawn give the shearing forces at all points.

If the load shifts its position, we may draw a new moment curve and then complete the diagram; but we shall presently show that a law holds for two continuous spans similar to the one advanced for a single span.

29. Before proceeding farther we will show that it is possible, without extra work, to determine the position of B' and eliminate approximations. We will illustrate by a simple example; the proof made use of can be extended to any case. Let a beam of two spans, c and d , Fig. 11, have a single load on each span. The moment curve will be similar to $ACDB$, the one represented. Let us suppose, for an instant, that there is no bending moment over the pier. Then drawing AI and IB we should complete our figure, and, calling the area of the triangle $ACI = A$, of $IDB = B$, and the distances of the centres of gravity of these triangles, from the verticals

* Perhaps it would have been better to lay off ts below t .

through A and B, respectively \mathbf{a} and \mathbf{b} , we ought to have the proportion $\frac{\mathbf{A} \mathbf{a}}{\mathbf{B} \mathbf{b}} = \frac{c}{d}$. Since a bending moment over the pier does exist, this equation will not be true. Then change the lines A I and I B to A E and E B, moving on the vertical a distance I E = x .

We now have the area moments on one side proportioned to the area moments on the other, as c to d . But the area moments on the left are equivalent to

$$\mathbf{A} \mathbf{a} - \mathbf{A} \text{ I E} \cdot \frac{2}{3} c,$$

$\frac{2}{3}c$ being the distance of the centre of gravity of A I E from the abutment vertical. Also the area of A I E is $\frac{cx}{2}$. A similar relation exists on the right. Therefore we may state our proportion as follows:

$$\frac{-\mathbf{A} \mathbf{a} + \frac{cx}{2} \cdot \frac{2}{3} c}{\mathbf{B} \mathbf{b} - \frac{dx}{2} \cdot \frac{2}{3} d} = \frac{c}{d}.$$

Everything here being known except x , we obtain the distance which B' (Fig. 10,) should be below K', when c and d denote the spans, \mathbf{A} and \mathbf{B} the areas A' F' K' and K' P' C', and \mathbf{a} and \mathbf{b} the lever arms of their respective centres of gravity,

$$x = \frac{3(\mathbf{A} \mathbf{a} d + \mathbf{B} \mathbf{b} c)}{cd(c + d)} = \frac{3}{c + d} \left(\frac{\mathbf{A} \mathbf{a}}{c} + \frac{\mathbf{B} \mathbf{b}}{d} \right).$$

$$\text{If } c = d, \quad x = \frac{3}{2c^2} (\mathbf{A} \mathbf{a} + \mathbf{B} \mathbf{b}).$$

Thus we can readily determine the position of B' , and thence the rest of the construction follows simply.

There is no failure when the beam happens to be horizontal over the pier B , for then MA and NC are each zero, and therefore area $C'P'D'$. $d l =$ area $K'B'D'$. $c k$, or $K'B'G'$. $b h = A'F'G'$. $a g$.

If great accuracy is not required, and, in any case, after a little practice, one can determine the positions of the centres of gravity, and hence the area moments, without dividing the areas into simpler portions.

The curves of the two spans might be constructed separately, as we should do for detached spans; but, in this case, we must have the same value of H for both curves, and they must coincide on the vertical through the centre pier. Therefore, in drawing the curves, we could start from K' , or any other point on the centre vertical, and work each way. Indeed, the curves might cross the horizontal line through C' , and can be transferred, at any time, if desired, to that line, by measuring off ordinates, either above or below it, so that $A'B'$ and $B'C'$ shall coincide with or become the horizontal line. Most authors who show any moment curves for girders draw them in this way. The construction of the curve for each girder by a separate stress diagram will be shown presently, in an example of four continuous spans.

30. If we are dealing with a continuous girder of two spans, we can find the bending moment over the centre pier, when each span is loaded *throughout its whole extent*,

with either the same or a different weight per foot run, by means of what is known as "Clapeyron's Formula," or the "Theorem of the Three Moments." This formula, as applied to two spans, resting on abutments at their extreme ends, but continuous over the pier, is—the bending moment

$$M = \frac{w_1 l_1^3 + w_2 l_2^3}{8(l_1 + l_2)} = \frac{W_1 l_1^2 + W_2 l_2^2}{8(l_1 + l_2)};$$

in which w denotes the weight per foot run, l the span in feet, W the weight of span and load, and the subscript numbers apply to the two spans. Dividing M by H from the stress diagram, in the same units of weight in which w was taken, we shall have the length in feet of the ordinate below the moment curve at the vertical from the pier. This formula only applies when *each span is uniformly loaded*.

31. Let us now make practical application of this method to a truss of two spans, one of 80 feet and the other of 100 feet, represented in Fig. 12, continuous over the pier. Let each truss weigh $2\frac{1}{2}$ tons per panel of ten feet, or 500 lbs. per foot, and let the rolling load be 1,000 lbs. per foot of one truss, or one ton per foot for the bridge. A panel weight for one truss will be, maximum $7\frac{1}{2}$ tons, minimum $2\frac{1}{2}$ tons.

Take 1-2 = 135 tons, the weight of both spans when fully loaded; divide 1-2 into portions of $7\frac{1}{2}$ tons, with end portions at 1 and 2 of $3\frac{3}{4}$ tons at A and C. Take a point 0, preferably opposite the middle of 1-2, and at a distance

in this figure of 50 tons. Since the truss is drawn as $12\frac{1}{2}$ feet high, it will simply be necessary to multiply the ordinates to the moment curves by *four*, to obtain the stresses on the chords, and this can be done, without multiplication, by measuring the ordinates by the proper scale. Leave out the end portions of $3\frac{3}{4}$ tons which come directly upon the abutments, and, commencing at A', draw the moment curve A' M C' parallel to the several lines connecting 0 with the points of division of the load line. Only the extreme lines radiating from 0 are drawn, as the remainder would only confuse the figure and tend to render the point 0 uncertain. Now calculate M B', either by the formula for determining x or by Clapeyron's formula, by which we have

$$MB' = \frac{M}{50} = \frac{\frac{3}{4} \cdot 80^2 + \frac{3}{4} \cdot 100^2}{50 \cdot 8 (80 + 100)} = 15.75 \text{ ft.}$$

Draw A' B' and B' C'. The figure A' M C' B' encloses the ordinates for bending moment when both spans are fully loaded. Draw 0-3 and 0-4 parallel to B' C' and B' A'; lay off 2-3 at cd and 1-4 at ae ; draw df and eg at an inclination of $7\frac{1}{2}$ tons to a panel, and the figure $cdfgeabc$ encloses the ordinates for shearing force when both spans are fully loaded. The supporting force at the pier $= bf + bg$. The detailed reasons for these constructions can be readily deduced from the case, before given, of a single span.

Next, remove all of the rolling load from A B, including, in this figure, the load on B; the load line will extend

from 2 to 5, and the extreme radiating lines are also drawn here. Use the moment curve $C'M$, and add the part from M to A'' . Find MB'' as MB' was found, simply changing $\frac{3}{4}.80^3$ to $\frac{1}{4}.80^3$, and draw $A''B''$ and $B''C'$. Find anew the supporting forces, and lay off ch and ak ; draw hi at an inclination of $7\frac{1}{2}$ tons to a panel, and kl at an inclination of $2\frac{1}{2}$ tons to a panel, completing the shearing diagram for this position of the load.

Next, remove the remaining portion of the rolling load from the span BC ; and now take the portion of the load line from 5 to 6. As the part $A'M$ of the moment curve applies to the first span, add the portion MC'' , and, finding B'' , complete the figure. MB'' will be, in this case, exactly one-third of MB' . The lines limiting the ordinates in the diagram of shearing force will be mn and pq . We also take the curve $A'MC''$, which represents the case of the shorter span covered with the rolling load, not including the point B , and the longer span unloaded, and, determining $A'B'''$ and $B'''C''$, find the supporting forces and thence the lines rs and tu .

Each one of the moment curves might have been drawn independently; but, by the method here carried out, of passing them all through the point M , two complete curves have sufficed for four different positions of moving load; and, in any case of girders with horizontal chords, these two curves are sufficient. The two curves might have passed through M without coinciding for one panel as in this figure, in which case the point B would have been relieved of one half of its rolling

load when one truss was unloaded, and some readers may prefer such a treatment. We should then require a new spacing of the load line.

The moment curve $M D'$ on the right and the dotted lines for shearing force apply to the particular cases where the span from C to D has upon it no moving load, the load for one set of lines covering $B D$ alone, and for the other set extending from A to D . In the first case the required point on the centre vertical was found to be just below B''' , as drawn, and in the second case a little below B'' . The light dotted lines from A'' to M , C' to M , D' to M , and from M and D' to E , show the different areas used in finding the different values of x . In the diagram for shearing force, $y v w$ and the dotted line between $q p$ and $k l$ are the limiting lines for the ordinates for a moving load over $B D$ alone, while $x z g$ and the dotted line between $t u$ and $e g$ determine the shearing ordinates for a moving load over $A D$.

32. A little study of the curves for bending moment, both those drawn for the partial and those for the complete load, will show that, for the given intensities of load, all the possible curves, if drawn to pass through M , will lie between $M A'$ and $M A''$ on the one side and $M C'$ and $M C''$ on the other: also, that the maximum bending moment which tends to make the truss concave upwards occurs when one span is fully loaded, the other being at the same time without travelling load. This fact might be anticipated, since the addition of a load on one span

will tend to diminish the deflection of points on the other. Since the worst bending moment over the pier must occur when both spans carry their heaviest loads, it is evident that $M B'$ is the longest ordinate for the point B ; conversely, $M B''$ must be the shortest ordinate, as the curve to which it relates represents the lightest possible load. All values of x will therefore lie between $M B'$ and $M B''$.

As $A' M C'$ and $A'' M C''$ are the limiting curves, we have also the extreme deviations of the points of contra-flexure, and, from the positions of these points, can readily determine the portion of each chord subject to tension alone, to compression alone, and the portion which has to be designed to withstand both stresses, as the load shifts its position. It will be noticed that the point of contra-flexure for the 100 ft. span shifts from the second panel from B , when only that span carries the moving load, to the fourth panel from B , when only the other span is fully loaded; while, for the 80 ft. span, the point of contra-flexure shifts from the second panel from B to the seventh panel from B under similar variations of load. The influence of the longer span on the shorter is very marked, as, when the longer one is fully loaded, the unloaded span presses at A with only the weight represented by $a k$. A check on the accuracy of construction is found in the fact that, when both spans are loaded and both unloaded, the points of contra-flexure occur at the same place. For a truss with parallel chords we require simply the curves $A' M C'$ and $A'' M C''$, combined, as has been

done here, with the lines which meet at B' , B'' , B''' and B'''' .

33. Let us now discuss the diagram for shearing force. In the first place, the dotted lines in the stress diagram are the ones drawn parallel to those diverging from the pier vertical in the moment diagram, and thus we determined the points marked k , q , e , t , r , m , x , etc.

We shall get the most pressure on the abutment C when BC is loaded and AB is not; the supporting force is then ch , and the shear on the two spans will be given by ordinates, at the *middle* of each panel, to the lines hi and lk . If the load extends over both spans, the supporting force falls to cd , and we determine the shear by drawing df and eg . If neither span has any rolling load upon it, we find the pressure at C to be cm , and we then draw mn and pq ; finally, if AB alone carries the rolling load, the pressure at C becomes cr , and the shearing diagram will be completed by the lines rs and tu .

Again: if the rolling load, at first extending entirely from A to C, moves off from the portion CD, the supporting force at C diminishes from cd to cx , and the shear will be given by ordinates to the lines xzg , etc., the point z occurring in the first lightly loaded panel D. If the rolling load covers BD, but the part on AB is supposed to be removed, the supporting force at C will immediately increase to cy , and the bounding lines for the ordinates will now be yvw , etc. As it is manifest that hi and mn are the limiting lines for the extreme cases of load over

B C alone and load over neither span, and as the load may cover any number of panels, from one to ten, from B towards C, the lines similar to $y v w$, for the different positions of the load, will shift between $h i$ and $m n$, and the point v will move on a curve, found to be a parabola, from the middle of one end panel to the middle of the other in the span B C. The ordinate to this curve will give the maximum possible shear in any panel for a load advancing from B. At the same time the line for the unloaded span moves between $k l$ and $p q$. Draw the parabola $n v h$ by § 10, commencing in the middle of the end panels.

If a load had advanced from A, over A B, and then extended from B towards C, we should have obtained, by exactly the same reasoning, a parabola, traced by the point z , on the tangents $d f$ and $r s$. As the ordinates to this parabola, above the line $b c$, are less than those to $h v n$, the latter only need be considered.

If a rolling load advances from C, the span A B being unloaded, the pressure at C increases from $c m$ to $c h$, and the different limiting lines for shear will move between $h i$ and $m n$; but, as the inclinations of the lines which correspond to $y v$ and $v w$ will be reversed, since C D now is loaded and B D is not, the point j at the angle will, like v , trace a parabola, from the middle of the panel near m to the one at i , of the opposite curvature. If, at the same time, A B is loaded and a load advances from C towards B, we find the parabola drawn in the figure from r to f . As this one includes the former, it is the only one needed.

While the load is shifted as above, the line in the other span vibrates between the parallels kl and pq in the one case, or tu and eg in the other.

34. The two parabolas hvn and rjf then limit all the ordinates for shearing force in this span, for every position of moving load, the portion of the parabola hvn which lies above bc giving the maximum shearing stress upwards, and requiring diagonals sloping one way, depending upon whether the truss has ties or struts for diagonals, and the part of rjf which lies below bc giving the maximum shearing stress downwards, and requiring braces sloping in the opposite direction. Upwards and downwards are relative terms, and are used on the supposition that the shear is taken on the right of the plane of section as shown in Fig. 6, enlarged view of panel $NOQP$. A similar construction supplies the required parabolas for the span AB , and thus all possible positions of the travelling load are provided for. It will be noticed how the counterbracing is shifted from the middle of the spans towards the free ends.

The desire to have the diagrams clear, while they are on so small a scale, forbids the drawing of moment curves and lines of shear for various positions of the load; but, if the reader will construct a figure for himself, with the load shifted, panel by panel, for a few panels, he will perhaps more readily see the truth of the statements here made as to the limiting values of bending moment and shearing force. Our object has been to set forth the

method to be pursued in designing a series of trusses by diagrams, and to explain sufficiently at length to enable any one using the method to satisfy himself of its applicability.

The two tangents mn and fd must intersect on bc , as they apply to the cases of uniform loads over both spans, and the usual relations between maxima and minima bending moments and shearing forces must also hold good. The different parts of the chords under different stresses, determined by the limiting positions of the points of contra-flexure, are shown in the figure, the portions always in tension being drawn with fine lines, the portions always in compression being represented by heavy lines, and those portions liable to undergo both stresses having double lines.

35. Remember, that, while the full lines in this figure show all of the curves and diagrams required for a full discussion of a continuous girder with horizontal chords, a truss with curved or inclined chords necessitates the use of a moment curve for each position of the load, to be combined with the shearing diagram, as explained in § 15. Also, Clapeyron's formula can be applied only when each span has some *uniform load throughout its extent*; when the load is partial or is irregularly distributed, find x by § 29. Find the stresses on the diagonals and verticals by § 11 or § 15, as the case may be.

If the two spans are equal, the number of lines becomes less, as B'' and B''' will coincide, and only the shearing diagram for one span need be drawn.

CHAPTER IV.

CONTINUOUS GIRDER OF MANY SPANS.

36. This graphical method is perfectly applicable to continuous girders, having any number of spans, of any lengths, and loaded in any manner. The example which we have chosen, see Fig. 13, shows four spans, of successively 80, 100, 50 and 40 feet, loaded as represented, with a load of the same intensity as given in the previous example, viz.:—from L to M and N to P, travelling load of five tons per panel, and steady load throughout, from A to E, of two and one half tons per panel.

To prevent the load line and stress diagram from occupying too much space, as well as to show the perfect practicability of drawing separate moment curves for each span, as we should do for single trusses, we have laid off the load lines of the longer spans independently, but have taken the same value for H in all of the diagrams, and this *must* be done. The stress diagram for the 80 ft. span is 012; the marks of division show the weights on the respective panel joints. Starting from A' , draw the moment curve for this span, terminating at B' . From B' draw the moment curve for the 100 ft. span, by lines parallel to those which would complete the stress diagram 0' 34, 3-4 being the load on this span, the curve ending at C' . As the last two spans are short, draw 5-6 equal to

the load on both spans, and then construct $C'D'E'$, as has been done in previous examples. Now draw $A'B'$, $B'C'$, $C'D'$ and $D'E'$. Compute the areas between each of these lines and the respective moment curves, and determine the position of the centre of gravity of each area. Those areas which are not simple parabolic segments can be divided, as explained in § 27.

37. Now we have to determine, in the same way as we found x for two spans, the distances x , y and z , or $B'F$, $C'G$ and $D'I$, the ordinates at the piers, required to complete the diagram for bending moments. Let the spans, commencing with AB , be l_a , l_b , l_c , l_d . Let the areas be represented by **A**, **B**, **C** and **D**. Let the distance of the centre of gravity of **A** horizontally from A be a , and from B be a' ; let b and b' , c and c' , d and d' denote the similar distances for **B**, **C** and **D** from the verticals on their left and right.

Then, considering the two spans AB and BC , we must have, (see § 29,)

$$\frac{Aa - \frac{x}{2} \cdot \frac{2}{3} l_a^2}{B'F C' \cdot \frac{2}{3} l_b + F C' G \cdot \frac{1}{3} l_b - Bb'} \quad \text{or} \quad \frac{Aa - \frac{x}{3} l_a^2}{\frac{2x + y}{6} l_b^2 - Bb'} = \frac{l_a}{l_b} \quad (1.)$$

$$\frac{Bb - \frac{x}{2} \cdot \frac{1}{3} l_b^2 - \frac{y}{2} \cdot \frac{2}{3} l_b^2}{\frac{y}{2} \cdot \frac{2}{3} l_c^2 + \frac{z}{2} \cdot \frac{1}{3} l_c^2 - Cc'} \quad \text{or} \quad \frac{Bb - \frac{x + 2y}{6} l_b^2}{\frac{2y + z}{6} l_c^2 - Cc'} = \frac{l_b}{l_c} \quad (2.)$$

$$\frac{Cc - \frac{y}{2} \cdot \frac{1}{3} l_c^2 - \frac{z}{2} \cdot \frac{2}{3} l_c^2}{\frac{z}{2} \cdot \frac{2}{3} l_d^2 - Dd'} \quad \text{or} \quad \frac{Cc - \frac{y + 2z}{6} l_c^2}{\frac{z}{3} l_d^2 - Dd'} = \frac{l_c}{l_d} \quad (3.)$$

Equations (1.) (2.) and (3.) may be reduced to

$$(l_a + l_b) x + \frac{l_b}{2} y = 3 \left(\frac{A a}{l_a} + \frac{B b'}{l_b} \right) \quad (4.)$$

$$\frac{l_b}{2} x + (l_b + l_c) y + \frac{l_c}{2} z = 3 \left(\frac{B b}{l_b} + \frac{C c'}{l_c} \right) \quad (5.)$$

$$\frac{l_c}{2} y + (l_c + l_d) z = 3 \left(\frac{C c}{l_c} + \frac{D d'}{l_d} \right) \quad (6.)$$

These equations may be extended to any number of spans by commencing with (4.), ending with one like (6.), and writing similar equations to (5.) a sufficient number of times to make in all one less equations than the number of spans. If $l_a=l_b=l_c$, etc., the equations simplify a little.

To show that no difficulty exists in the solution of the above equations, apply them to the above case, and, since the second members are known quantities, denote them by P, Q and R. Then

$$180 x + 50 y = P \quad (7.)$$

$$50 x + 150 y + 25 z = Q \quad (8.)$$

$$25 y + 90 z = R. \quad (9.) \text{ Multiply (8) by 3.6}$$

$$\underline{180 x + 540 y + 90 z = 3.6 Q.} \quad \text{Subtract (9.)}$$

$$\underline{180 x + 515 y = 3.6 Q - R.} \quad \text{Subtract (7.)}$$

$$465 y = 3.6 Q - R - P$$

$$y = \frac{3.6 Q - R - P}{465}.$$

Substitute in (7.) and find x ; then in (9.) and find z .

38. In the practical solution of this example, with the given load distributed as shown in Fig. 13, we meet with

one peculiar result: the value of z is found to be *minus*, that is $D'I$ must be measured off from D' upwards. This fact shows that there is no point of contra-flexure on the forty feet span, and no negative moment over the pier D . The load on the 100 ft. span has a tendency to lift the bridge off from the pier at D , and consequently the pressure there will be found to be small. If the point I had come on the straight line joining G and E' , the bridge would have been lifted entirely clear of the pier D , and, if I had come above the line GE' , another solution would have been required with the pier D considered as removed, making CE one span, or else the truss would have required bolting down at D .

39. Having drawn $A'F$, FG , GI and IE' , draw, in the respective stress diagrams, lines $0'7$, $0'8$, $0''9$ and $0''10$, parallel to them, cutting off the supporting forces on the several piers arising from each truss, and then complete the diagrams for shearing force. We shall find that, by drawing the stress diagrams separately, as has here been done, we get the supporting force on any pier, carrying the ends of two spans, in two portions, one belonging to each span; and hence the point of termination of the line for shearing force on the vertical through the pier is at once known. Thus $1-7$ equals ap and $7-2$ gives bf , $3-8$ gives bm and $8-4$ determines cg . The pressure on B is $bf + bm$. Notice that, as di and dk come on opposite sides of d , the pressure on D , with this load, is $dk - di$.

40. If a continuous girder of several spans is to be completely discussed, Clapeyron's formula may be usefully applied to the determination of bending moments over the piers, subject always to the restriction of uniformity of load; as before remarked. Denoting the bending moments at successive points of support by M_0, M_1, M_2 , etc.; the spans by l_1, l_2, l_3 , etc., in feet, and the respective loads per foot by w_1, w_2, w_3 , etc., we may write this formula :

$$\begin{array}{l} M_0 l_1 + 2 M_1 (l_1 + l_2) + M_2 l_2 = \frac{1}{4} (w_1 l_1^3 + w_2 l_2^3), \\ M_1 l_2 + 2 M_2 (l_2 + l_3) + M_3 l_3 = \frac{1}{4} (w_2 l_2^3 + w_3 l_3^3), \\ \text{etc.,} \qquad \qquad \qquad \text{etc.} \end{array}$$

We have in all one less equations than there are spans. As the ends of the girder are usually free, there will be no bending moments at the two abutments, or, for n spans, M_0 and M_n will equal zero, and there will be left $n - 1$ unknown bending moments to be determined from $n - 1$ equations.

CHAPTER V.

PIVOT ~~BRIDGES~~ OR DRAW SPANS.

41. Having shown the method of treatment for the fixed spans of a bridge, either continuous or discontinuous over the piers, we wish to complete the investigation by discussing what is called the *draw span*. This span is capable of being turned horizontally on a pivot at its middle, so as to open two channels, one on either side of the centre pier, for the passage of vessels. When it is open, it acts as two beams or trusses, each fixed and horizontal at one end, with a uniform load, arising from its own weight, over its whole extent. The two portions are usually, though not necessarily, equal in length, and they balance on the pivot and turntable. When the draw is closed, it may be elevated by cams or wedges under the free ends so as to bring a greater or less pressure upon those piers, or it may simply swing over its wall plates or seats, without practically pressing on the piers until a travelling load comes upon it, or finally it may be secured by horizontal locking bolts, so arranged that, while they do not bring the draw any more closely in contact with the wall plates, they prevent one end from rising from its seat when the travelling load first comes upon the other end.

42. We have, then, several cases with which to deal.

1st. If the pivot or draw span is supported at its ends, when closed, so that the moment over the centre pier is the same as exists in a continuous girder of two equal spans, (in which case it is necessary that each end support shall carry, when there is no travelling load on the draw, *three eighths* of the weight of one *span*,) the draw, when closed, will be circumstanced precisely like a continuous girder of two equal spans. To obtain the required amount of supporting force it is necessary to provide lifting cams with powerful leverage, or to use hydraulic jacks. If then we draw our diagrams for two equal continuous spans as described before, we have only to add the moment curve and diagram for shearing force for the draw *open*. A consideration of the method given for a beam overhanging at one end, will show the construction in this case. Here the beam overhangs at both ends, and the two supports have become united in one, the beam balancing upon it.

43. Construct, if it has not already been done, the moment curve for the truss loaded with its own weight. Remember that the *end joints* each carry one-half of a panel weight. Therefore, from the points where the moment curve cuts the verticals from the extreme ends of the draw, draw lines parallel to lines in the stress diagram from 0 to the extreme ends of the load line, and these lines must cut the vertical from the centre pier in the same point. By reference to Fig. 14, we can see that the draw when open is in the condition of the beam A B C, if

the abutments A and B are removed. The moment curve will be $A'E'C'$, and $A'B'$ and $B'C'$ are tangents to the curve at its extremities. The ordinates to the moment curve, thus intercepted, will be, when multiplied by H , the bending moments at the joints.

Draw lines from the extremities a and c of the base line for shearing force to a point b , on the centre vertical, below the base line a distance equal to the weight of one span, or one-half of the load line, and the ordinates at the middle of the panels will show the shearing force when the draw is open.

The diagrams for this case are thus completed; that is, these lines just described are to be added to the curves, etc., required for two equal continuous spans. When the draw is open, there will be tension throughout the top chord and compression throughout the bottom chord, and braces will be required, all sloping one way, from the centre to the end. The stresses when the draw is closed, and the direction of the braces required, will be as stated in §§ 32, 34. If the supporting forces at the ends exceed or fall short of the amount before stated, three eighths of the weight of one span, the case requires a different treatment. From the power applied to the cam or jack the actual amount of the supporting force may be approximated to, and the new state of affairs readily be classed under a case soon to be taken up.

44. 2*d*. A draw, as usually constructed, is screwed up at the centre, until almost the entire weight and bearing is

upon the pivot, and the ends of the truss scarcely do more than touch the bearings on which they close, as is shown by the immediate tilting up of one end of a draw when a train enters the other end. The truss may then practically be considered as poised on the centre when shut and unloaded, with the same stresses as when open. Let $A B C$, Fig. 14, represent the draw, closed, poised on the pivot B , and barely in contact with the abutments at A and C . The curvature in the figure is exaggerated; but every draw is practically curved in this way when supported in the middle and deflected under bending moments arising from its own weight, even when it is actually straight and horizontal, as is proved by the existing tension in the top chord and compression in the bottom chord; and the points A and C can be brought to a level with B only by a *camber* previously induced in the truss.

When a rolling load passes on at D , the farther end F rises, the truss is carried by two supports, with one end overhanging, and the construction of the diagrams will follow the method described in § 20. As described in § 43, $A'E'C'B'$ is the diagram for bending moment of $A B C$, the draw open, and also for the draw closed but not raised at the ends by cams. By drawing $T'D'$ as the new portion of the curve required by the load $T D$, we have $D'T'E'C'$ as the new moment curve. Any load on $D E$ will not alter the bending moment on $E F$, and therefore $C'B'$ is still one of the lines, and $B'D'$ must be the other required to complete this diagram. The point of contra-flexure near T' is readily seen. A line parallel, in

the stress diagram (not shown in this figure), to $D'B'$, will give us ad , the supporting force at D , and the lines dte with bc will determine the ordinates for shearing force.

45. The further end of the draw will rise still higher, as the load advances over the first span, and finally reaches the centre pier. The further progress of the load will cause F to move down again, but it will not come down to the bearing on G , until the train or other moving load has advanced a certain, often a considerable, distance over the free span, sometimes more than one-fourth of the space from the centre pier. The important point to be determined is the position, S , of the front of the rolling load on IKL , when the end, L , of the beam is just forced down to its abutment.

Draw through K a tangent QKM to the beam at that point. When the beam rests on the abutments the deflections at the ends from the tangent at K are ML and QI . From the similar triangles MNL and PQI , made by vertical lines through I and L and lines perpendicular to QM , any ratio which exists between ML and QI will hold between NL and PI . If we add IR to PI , and subtract its equal, LO , from NL , we have an entirely similar proportion to the one deduced for a two-span continuous truss, namely :

$$NO : PR = KN : KP = KO : KR = 1, \text{ or } NO = PR.$$

Now ML is proportional to the *area moment* on the

span KL , as explained in §§ 24, 25; QI is proportional to the area moment of the span KI , and $LO = IR$, is proportional to the original area moment of either span, before any rolling load has come upon it, or to the area $C'B'E'$ multiplied by the distance of its centre of gravity from the vertical through L . Call this area moment Cc .

46. The curve $I'E'L'$ being drawn, the condition that the end L shall rest upon the abutment will, therefore, be satisfied when the area moment to the left of $E'K'$ plus Cc equals the area moment to the right of $E'K'$ minus Cc . This equation will determine the position of K' , as in former cases. But note that, when we find a point K' , satisfying the above condition, so placed that a tangent to the curve at L' , or a line parallel to the last radiating line in the stress diagram to the *extremity* of the line of loads, cuts $E'K'$ above K' , the span has risen from the abutment. For it is necessary that a parallel to $K'L'$ should cut off some portion of the load line to give any supporting pressure to L . When one end of the span is off the abutment, see § 44.

To find the distance $E'K'$ or x for every position of the end of the travelling load between S and L :—draw a straight line from I' to E' , and one from E' to L' ; call the areas between these lines and the moment curve respectively A and B , A being the area belonging to the side which is entirely loaded, and the distance of their centres of gravity, horizontally from I' and L' , a and b . Then, by the same course of reasoning given in § 29, Fig. 11,

and from the equation stated above, we have, letting l equal either span,

$$Aa - \frac{x l^2}{3} + Cc = \frac{x l^2}{3} - Bb - Cc.$$

$$x = \frac{3}{2l^2} (Aa + Bb + 2Cc).$$

47. If the curves are drawn as usual in these pages, $I'E'$ being common to all of the curves for movements of S , the head of the load, towards L , we have Aa and $2Cc$ constant, as well as the divisor $\frac{3}{2l^2}$; so that, for each new position of the load, we have only to calculate Bb , divide it by $\frac{3}{2l^2}$, and add the quotient to the previous constant quotient, to obtain x , equal $E'K'$.

The shear is then readily obtained; for the load from I to S it is limited by the lines $ikks c$. When the load extends to L we have the symmetrical curve $I'E'V'$ and the shearing diagram $auwvc$. The increase of rolling load from S to L diminishes the supporting force at I from ai to au , and manifestly the supporting force at I will be a maximum when only the span IK is covered by the travelling load.

The points of contra-flexure will be found nearer the ends for given loads than in a continuous girder of two spans, as might be expected; since the load has to overcome or neutralize first the initial negative moment of flexure. And, consequently, the bending moment over the centre pier is greater than in a continuous girder. Most draw trusses have a greater depth at the centre

pier than at the ends, thus diminishing the stress on the chords at that point below the amount which would exist for parallel chords.

48. It will perhaps be more convenient to show now, before we give the entire diagrams for a pivot bridge or draw span, the modification which is introduced by case

3d. Where the ends of the draw are prevented by locking bolts from rising from the abutments, the action will be similar to that produced by hanging an additional, but variable, weight at F, just sufficient to bring F in contact with G. The greatest weight will be required when the rolling load extends from D to E. It is readily seen that, if F must always remain on G, the condition required for case 2, instead of being limited to loads which give a pressure on L, must be satisfied for every position of the load from D to F; that is, we must always have

$$x = \frac{3}{2l^2} (Aa + Bb + 2Cc).$$

This value of x determines K' . Now if the line to be drawn in the stress diagram, parallel to $K' L'$, passes beyond the end of the load line, the additional length of load line required to meet it will be the upward pull on the bolt at L, and this pull will increase, commencing with zero at S, until the rolling load retires to K, and will then diminish to zero again when the rolling load entirely moves off at I. This modification makes the only differ-

ence in the treatment of cases 2 and 3. In the shearing diagram, the amount of upward pull on the locking bolt, being opposed in direction to a supporting pressure, is to be laid off from c , downwards, and, from its lower extremity, will then be drawn a line parallel to, and taking the place of, $c s b$ or $c s k$, etc. This pull affects the stresses on all portions of the draw and shifts the points of contra-flexure.

49. 4th. Suppose that the draw, instead of being circumstanced as in case 2, is raised at the ends by cams or jacks, but that the supporting forces do not equal those required by case 1, where A and C are on the same level with B. Find, from the known power applied to the cams, the amount of the supporting force at each end when the draw is unloaded. Lay off these amounts, each on the proper end of the load line, and draw lines from the two points of division so obtained to the point in the stress diagram usually marked 0. Construct the moment curve for the spans unloaded, and then draw lines, from the extremities of the curve to the centre vertical, parallel to the lines just drawn in the stress diagram. The ordinates so cut off will be the ones required to determine the bending moments on the closed and unloaded draw, and the area moment on one side, (or the moments on each side, if not the same, owing to different supporting forces at the ends,) will represent the quantity to be used, instead of Cc , in cases 2 and 3.

The ends of the draw may be raised so as to give a

pressure of more than three-eighths the weight of one span on each abutment. It will then be necessary to determine the amount and proceed by the steps just described.

50. A general case might be made of the difference of level between the centre pier and the abutments. If A and C are above B, we shall have the last case. If A and C are sufficiently above B, we shall have no pressure on B and hence one single span. If A and C are level with B, Cc will equal zero and we shall have case 1. If A and C are below B, we shall have cases 2 and 3. An equation similar to those which have preceded, formed by the introduction of two terms in Cc , one for each span, into the value for x given in § 29, would probably admit of this general discussion.

51. If we take a draw span; such as is represented in Fig. 15, we may proceed to find the stresses on the different parts, under the supposition that holding down bolts are used; in other words we may apply case 3.

Let the draw be 240 feet long, making two spans of 120 feet each, ($= l$), divided into twelve panels of 20 feet each; let the height at the centre be 25 feet, and at the ends 20 feet. The dead weight is assumed to be 10 tons to a panel, and the travelling load is also 10 tons to a panel. An increase in the number of panels and an unequal distribution of dead and live load would not have rendered the construction more difficult, but would have confused the figure. In order to have the moment curves

well separated, with the present scale, we have taken H as 60 tons only.

To proceed to the construction: 1-2 represents 240 tons, the maximum load. Take 0 at a distance of 60 tons, opposite the middle of 1-2. Draw, if convenient, $A'MC'$, for the draw entirely loaded, by commencing at C' with a line parallel to 3-0, and ending at A' with a line parallel to 4-0, 20 tons being carried on each joint, except A and C, which carry 10 tons each. Next, through the point M, draw $A''MC''$ for the draw unloaded; it may be convenient to use one of the sides of the polygon already drawn through M, as, for example, the one parallel to 0-7, and we may, therefore, construct each way from this side, as shown in the figure, taking 10 tons on each joint, and terminating at C'' and A'' with lines parallel to 0-8 and 0-9. As five tons, when the draw is free or is open, rest on A and C, draw from A'' and C'' the lines $A''B''$ and $C''B''$ parallel to 0-5 and 0-6. The ordinates between $A''MC''$ and $A''B''C''$ are proportional to the bending moments at different points of the draw open, or closed and unloaded. Calculate the area $A''MB'' = C$, find the distance of its centre of gravity from the vertical through A, and denote it by c . (See § 27. If $A''M$ may be considered a close approximation to a parabola, $c = \frac{3}{4} AB$.)

Draw a straight line from A' to M and compute the area enclosed between the curve $A'M$ and the line just drawn; call it A ; then multiply by the distance a , =

$\frac{1}{2}$ A B, of its centre of gravity from A. To find, for the curve A' M C', M B' =

$$x = \frac{3}{2l^2} (\mathbf{Aa} + \mathbf{Bb} + 2\mathbf{Cc}),$$

we have $\mathbf{Bb} = \mathbf{Aa}$. Having made this computation, lay off M B', and draw A' B' and C' B', determining the bending moment for the draw closed and entirely loaded. Draw a straight line from C'' to M, compute \mathbf{Bb} for this curve, and, using \mathbf{Aa} as before, find by the same formula, M B''', and draw A' B''' and C'' B''', as well as A'' B''' and C' B''', determining the bending moment for the draw when one span is loaded and the other unloaded.

52. Next draw from O lines parallel to those which meet at B', B'' and B''', and lay off the supporting forces thus found at *a* and *c*. These reactions will be *ae* and *cd* when both spans are loaded, *ak* and *cn* when A B is loaded and B C unloaded, and *cg* and *al* when the load is upon B C alone. It is plain that the pressure upon the abutment at A will be greater when A B alone is loaded, than when a load over a portion or the whole of B C acts as a partial counterpoise, and the maximum pressure at A, = *ak*, will occur when the whole of A B is loaded. A weight between A and B will tend to raise C from the abutment, and will cause a shearing stress on that locking bolt. This stress will increase as the load on A B increases, until all the weight is added, but, as soon as the load passes beyond B toward C, the stress on the bolt at

C will diminish. Therefore cn is the maximum shear on the bolt, and is drawn below ac as a negative supporting force, because the line drawn from 0, parallel to $B'''C''$, to determine it, strikes *beyond the end* 6 of the load line to that amount. At the other end, $5-10 = al$.

Now draw ah and ch , at an inclination of ten tons to a panel, cutting off bh , equal to the weight of BC or AB unloaded; ahc will be the shearing diagram for the unloaded draw, either open or closed. Draw ef and df , at an inclination of twenty tons to a panel, and $ae f d c$ will be the shearing diagram for the draw closed and entirely loaded. Then ki , parallel to ef , and nm , parallel to ch , will be the lines required for the diagram when AB is loaded and BC unloaded; while gi and lm will apply to the reverse case. As will appear later, parabolas drawn on the tangents lp and pf , gr and rh , having points of tangency at the middle of the first panels from each point of support, will complete all *necessary* lines in the shearing diagram. To easily construct these parabolas, see § 10.

53. As the draw in this example has an inclined upper chord, we shall need other moment curves. Suppose the load, advancing from A, extends to and includes G. Using the portion $C''M$ for the lightly loaded side of the draw, add the two sides of the polygon which will complete $G'MC''$, compute x for this curve as was done for the others, and draw lines from G' and C'' to the middle vertical, meeting it at a point a little removed from B'' towards B''' ; for the weight added at E and G will in-

crease the bending moment over the point B. The lines for shearing force, (not drawn in the figure,) starting from a point above a , will run to t , and thence, at a less inclination, to a point below m ; on the other span the line will lie between $h c$ and $m n$.

Next suppose that, instead of a rolling load from A to G only, we first load B C throughout and then add the load from A to G as before. We must now use the curve $G' M C'$, and the bending moment at the centre pier will be increased beyond the amount existing when only one span is loaded, so that the inclined lines will now meet the centre vertical between B''' and B' . Thus the two lines drawn from G' to the centre vertical are accounted for. Finding the supporting forces under the new condition of things, we shall have, in the diagram for shearing force, the lines aw , wu , uz , and a line between and parallel to ig and fd . We thus find a greater negative shear on A B under this load than under the former.

Add a load on J. Draw $J' M$. The bending moment over the centre pier will be slightly increased, and we can construct, as we did from G' , the two lines from J' to the centre vertical, and in the shearing diagram we shall find, when B C also is loaded, the lines ay , yv , etc., as before. A load added to L will, in the same way, determine the point s . The curves starting from E' , G' , J' , L' and A' represent the successive increments of rolling load on E, G, J, L and P, and, as combined with $M C''$ or $M C'$, apply to the cases where B C is unloaded or loaded. All the lines to the centre vertical are not drawn, but enough

of them are shown to explain the action. The letters at the extremities of the curves are intended to indicate the last fully loaded point. A rolling load on B will be found not to alter the bending moment, hence the curve for P becomes the one from A'.

54. As the load advances from A to B then, the span BC being fully loaded, we shall find that the ordinates for the maxima stresses in the successive panels occur immediately in front of the load, and terminate in the points u, v, s , etc., which points will lie in a parabola, described on the tangents lp and pf , with tangent points in the middle of the first and last panels. If BC were *unloaded*, these ordinates would terminate in a parabola drawn on the tangents aq and qi , and shown in the figure as a dotted line; but, as the former parabola gives the maxima stresses in this direction, it alone need be drawn. A symmetrical one can be sketched on frn , for a load advancing from the other end, but it will not be necessary.

Similarly, if the load extends from A, past B, to V, we shall have the curve V' M combined with A' M, and, if only BV is loaded, the curve V' M combined with A'' M. A load on BV alone will cause a greater supporting force at C than when AB is also loaded; therefore the increments of load from B towards C, while AB is unloaded, will give us the points on a parabola drawn on hr and rg . The dotted parabola dm on the parallel pair of tangents below, belongs to the case of a load extending from A en-

tirely to the successive points on BC. All other loads moving from A towards C will give less values than those now obtained, and the maxima shears in all of the panels are thus determined by ordinates, at the middle of the panels, from abc to the parabola $lusf$ below, or to that portion of the other parabola gh above, abc . Finally, we make the draw span symmetrical, and so provide for moving loads in the other direction.

55. The point of contra-flexure, advancing from the outer end as a load enters upon the draw, will be seen to move no nearer the centre pier than the third panel from the end. Consequently KR will always be in tension, GB will always be in compression, while KD and GA must be designed to withstand either stress. The moment at the joint J, being the last moment which is always the same as that over the pier, will be resisted, if we take J as origin, by JK multiplied by the horizontal projection of the tension in KN, or, if we take K as origin, by JK into the compression in JG. Thus we determine the points K and G of the lengths RK and BG.

The maximum ordinate at any joint being readily selected from the figure $A'MC'C''B'A''$, and multiplied by H, if we divide by the height of the truss at that joint, we shall have the *horizontal* stress on that side of the joint not touched by the diagonal in action at the time. The horizontal stress in the inclined chord must be increased in the ratio of the actual length of that portion of the chord to the length of a panel horizontally. A ready

construction is to draw a horizontal line equal in length to the horizontal stress, from one end draw a line parallel to the portion of the inclined chord in question and limit it by a vertical line from the other end. The hypotenuse represents the desired stress on the inclined chord. A curved piece may be treated as straight between the two joints, for finding the direct stress ; its curvature introduces a separate bending moment on the piece itself.

56. Finally, to find the stresses on the diagonals and verticals :—compare § 15, etc. Take, for example, the pieces LQ and PQ. The maximum shearing stress in the panel LP will be the ordinate from ab to s . Lay off this ordinate at os in the lowest figure. This shear will be caused by a rolling load from A to L inclusive, together with one from B to C, (and is to be considered a positive or upward shear, as shown by the arrow in the panel, although the combination of the two spans of the draw brings this parabola below the line ab). The curve of moments will therefore be $L'MC'$, and the ordinates for bending moment, under that load, at L and P will be $L'N'$ and $P'Q'$; multiply these ordinates by H, and divide by LN and PQ respectively, thus obtaining the *horizontal* stress from N towards Q and the horizontal stress on PL. Lay off sL equal to the latter, and, drawing oQ parallel to NQ , make the horizontal distance of Q from o equal to the former. Ls and oQ are drawn to the left of the vertical os representing the shear, because the bending moment tends to make the truss convex

upwards; or the reverse of Fig. 6. If no error has been made, LQ when drawn will be parallel to LQ of the truss, and will give the amount of the existing stress, while the line marked $P-Q$, drawn vertically upwards from the point marked L , will be the stress on the vertical PQ . The remainder of the figure applies to the other pieces of the web, as shown by the letters. We shall thus obtain the stresses on all of the diagonals which incline from the centre pier down towards the abutment. BR will have upon it double the stress shown in the figure, as it resists the action of the inclined pieces in both halves of the draw. There remains the diagonal ST , required by the shear which arises in the panel SC when the span BC alone is fully loaded. The bending moment at S being then of the kind to cause convexity downwards, construct this figure on the right of the vertical at o . There will be no tension on SC , and we are consequently reduced to a triangle, giving $S-T$ and $C-T$ as drawn.

A study of the diagrams of Fig. 6, and the explanations therewith, will show what modifications would be introduced by the inclination of the bottom chord, the substitution of struts for ties, or of a load on the top chord for one on the bottom chord.

57. Without drawing additional diagrams we can probably determine, by inspection of Fig. 15, what changes would be effected in the draw by the removal of the locking bolts, bringing it under case 2, § 44. Both when the draw is entirely loaded, and when the rolling load is alto-

gether removed from the draw, there is no force exerted on the bolts. The absence of the bolt will therefore make no change in the position of B' and B'' . The point B''' , found when one span only is fully loaded, will be situated a little nearer M , owing to the omission of the moment over B caused by the pull on the bolt multiplied by the span BC ; the point of contra-flexure will therefore come somewhat nearer the centre pier, and the extent of each chord subject to but one kind of stress will be diminished. All of the values of x which would give any pull on the bolt, and which correspond to loads on any portion of RS , Fig. 14, will be slightly less.

In the shearing diagram we need to consider only the changes which take place in the two limiting parabolas for maxima values, $lv sf$ and hg . As $lv sf$ is the curve for a load advancing from A , while the other span is fully loaded, and as, under these circumstances, the holding down bolts cannot be in action, this parabola will not be changed. When BC , and it alone, is covered with a rolling load, the supporting force at C is diminished by the amount of the pull al on the abutment at the other end. Remove the bolt at A , and the point g will now be found to have moved farther from d by the amount al or cn . That is, to find g , lay off ng from c . This increase of supporting force at C will affect the shear at all points of the span, when BC is loaded, by just this amount, and therefore gi will move parallel with itself to the new distance from c just stated, and ml will coincide with ah . Therefore the

parabola hg will rise to its new tangents, increasing the shear in panels near C.

The coincidence of ml with ah , or its disappearance, will not affect the position of lv or sf , but we shall have to draw lm where it stands in this figure, to find this parabola. With these suggestions no difficulty need be experienced in making the diagrams for case 2.

CONCLUSION.

It will be noticed that we have not, in what has gone before, attempted to give different forms of trussing. We have rather endeavored to set forth the method plainly, and perhaps have been, for that reason, at times diffuse; a clear understanding of the line of procedure will enable one to apply it to any type of bridge desired. Where compound systems of trussing are to be used, it will probably be advisable to draw separate diagrams for the simple systems, and then combine the results. We have also, in the bridges used as examples, taken both the steady and rolling loads as uniformly distributed over the proper portions of the span. Any one who wishes to make the load heavier in one portion than in another, as is sometimes done when we consider the weight of a locomotive aside from the average weight of a train per foot, can readily change the divisions on the load line to correspond. Such a change in these plates, with their necessarily small scale, would have brought confusion into the stress diagrams, from the necessity for entire redivision of the load line at every change in position of the rolling load.

The same remark applies to the construction of all the moment curves or polygons in a figure with one common side, and to the proportions of live and dead load here taken.

Further, some may object to considering the panel joint under the head of the moving load as fully loaded, while the one next in advance carries none of this moving load. This practice has its advantages in easier construction of diagrams, and many authors adopt it; the shearing stresses thus found are slightly in excess of the real maxima stresses, erring a trifle on the side of safety. A different distribution of the load can be used with a little more work.

One who makes himself familiar with the preceding graphical method will find that it possesses within itself many checks on the accuracy of the drawings, some of which have been alluded to. Those who prefer to find the stresses on the various parts of a truss by direct calculation will find a graphical method a valuable check on their computations, and a complete diagram, for every position of the moving load, shows readily to the eye, and more advantageously than the discussion and interpretation of mathematical formulæ would show to most persons, the increase and decrease of stresses in different members, the change of bending moment, the shifting of points of contra-flexure, and any other possible points of interest. Diagrams also afford a ready means for the comparison of trusses. This method can probably be extended to more problems of the same class, as it is en-

tirely general in its treatment. It has sometimes been thought desirable to make the moment over the piers, of a continuous girder, equal to the moment at the centre of the spans, and these diagrams may render that object attainable. The determination of the proportions of a stiffening girder for a suspension bridge can be made by this method.

I.

Fig. 2.





Fig. 5.

Fig. 3.




Fig. 7.








Fig. 6.



Scale for Diagrams I to IV.

Fig. 8.







SCIENTIFIC BOOKS

PUBLISHED BY

D. VAN NOSTRAND,

23 MURRAY STREET & 27 WARREN STREET,

NEW YORK.

Weisbach's Mechanics.

New and Revised Edition.

8vo. Cloth. \$10.00.

A MANUAL OF THE MECHANICS OF ENGINEERING,
and of the Construction of Machines. By JULIUS WEISBACH, PH.
D. Translated from the fourth augmented and improved German edition, by ECKLEY B. COXE, A.M., Mining Engineer. Vol. I.—Theoretical Mechanics. 1,100 pages, and 902 wood-cut illustrations.

ABSTRACT OF CONTENTS.—Introduction to the Calculus—The General Principles of Mechanics—Phoronomics, or the Purely Mathematical Theory of Motion—Mechanics, or the General Physical Theory of Motion—Statics of Rigid Bodies—The Application of Statics to Elasticity and Strength—Dynamics of Rigid Bodies—Statics of Fluids—Dynamics of Fluids—The Theory of Oscillation, etc.

"The present edition is an entirely new work, greatly extended and very much improved. It forms a text-book which must find its way into the hands, not only of every student, but of every engineer who desires to refresh his memory or acquire clear ideas on doubtful points."—*Manufacturer and Builder*.

"We hope the day is not far distant when a thorough course of study and education as such shall be demanded of the practising engineer, and with this view we are glad to welcome this translation to our tongue and shores of one of the most able of the educators of Europe."—*The Technologist*.

Francis' Lowell Hydraulics.

Third Edition.

4to. Cloth. \$15.00.

LOWELL HYDRAULIC EXPERIMENTS — being a Selection from Experiments on Hydraulic Motors, on the Flow of Water over Weirs, and in Open Canals of Uniform Rectangular Section, made at Lowell, Mass. By J. B. FRANCIS, Civil Engineer. Third edition, revised and enlarged, including many New Experiments on Gauging Water in Open Canals, and on the Flow through Submerged Orifices and Diverging Tubes. With 23 copperplates, beautifully engraved, and about 100 new pages of text.

The work is divided into parts. PART I, on hydraulic motors, includes ninety-two experiments on an improved Fourneyron Turbine Water-Wheel, of about two hundred horse-power, with rules and tables for the construction of similar motors; thirteen experiments on a model of a centre-vent water-wheel of the most simple design, and thirty-nine experiments on a centre-vent water-wheel of about two hundred and thirty horse-power.

PART II. includes seventy-four experiments made for the purpose of determining the form of the formula for computing the flow of water over weirs; nine experiments on the effect of back-water on the flow over weirs; eighty-eight experiments made for the purpose of determining the formula for computing the flow over weirs of regular or standard forms, with several tables of comparisons of the new formula with the results obtained by former experimenters; five experiments on the flow over a dam in which the crest was of the same form as that built by the Essex Company across the Merrimack River at Lawrence, Massachusetts; twenty-one experiments on the effect of observing the depths of water on a weir at different distances from the weir; an extensive series of experiments made for the purpose of determining rules for gauging streams of water in open canals, with tables for facilitating the same; and one hundred and one experiments on the discharge of water through submerged orifices and diverging tubes, the whole being fully illustrated by twenty-three double plates engraved on copper.

In 1855 the proprietors of the Locks and Canals on Merrimack River consented to the publication of the first edition of this work, which contained a selection of the most important hydraulic experiments made at Lowell up to that time. In this edition the principal hydraulic experiments made there, subsequent to 1855, have been added, including the important series above mentioned, for determining rules for the gauging the flow of water in open canals, and the interesting series on the flow through a submerged Venturi's tube, in which a larger flow was obtained than any we find recorded.

Francis on Cast-Iron Pillars.

8vo. Cloth. \$2.00.

ON THE STRENGTH OF CAST-IRON PILLARS, with Tables for the use of Engineers, Architects, and Builders. By JAMES B. FRANCIS, Civil Engineer.

Merrill's Iron Truss Bridges.

Second Edition.

4to. Cloth. \$5.00.

IRON TRUSS BRIDGES FOR RAILROADS. The Method of Calculating Strains in Trusses, with a careful comparison of the most prominent Trusses, in reference to economy in combination, etc., etc. By Brevet Colonel WILLIAM E. MERRILL, U.S.A., Major Corps of Engineers. Nine lithographed plates of illustrations.

"The work before us is an attempt to give a basis for sound reform in this feature of railroad engineering, by throwing 'additional light upon the method of calculating the maxima strains that can come upon any part of a bridge truss, and upon the manner of proportioning each part, so that it shall be as strong relatively to its own strains as any other part, and so that the entire bridge may be strong enough to sustain several times as great strains as the greatest that can come upon it in actual use.'"—*Scientific American*.

"The author has presented his views in a clear and intelligent manner, and the ingenuity displayed in coloring the figures so as to present certain facts to the eye forms no inappreciable part of the merits of the work. The reduction of the 'formulae for obtaining the strength, volume, and weight of a cast-iron pillar under a strain of compression,' will be very acceptable to those who have occasion hereafter to make investigations involving these conditions. As a whole, the work has been well done."—*Railroad Gazette, Chicago*.

Humber's Strains in Girders.

18mo. Cloth. \$2.50.

A HANDY BOOK FOR THE CALCULATION OF STRAINS IN GIRDERS and Similar Structures, and their Strength, consisting of Formulae and Corresponding Diagrams, with numerous details for practical application. By WILLIAM HUMBER. Fully illustrated.

Shreve on Bridges and Roofs.

8vo, 87 wood-cut illustrations. Cloth \$5.00.

A TREATISE ON THE STRENGTH OF BRIDGES AND ROOFS—comprising the determination of Algebraic formulas for Strains in Horizontal, Inclined or Rafter, Triangular, Bow-string, Lenticular and other Trusses, from fixed and moving loads, with practical applications and examples, for the use of Students and Engineers. By SAMUEL H. SHREVE, A.M., Civil Engineer.

"On the whole, Mr. Shreve has produced a book which is the simplest, clearest, and at the same time, the most systematic and with the best mathematical reasoning of any work upon the same subject in the language."—*Railroad Gazette*.

"From the unusually clear language in which Mr. Shreve has given every statement, the student will have but himself to blame if he does not become thorough master of the subject."—*London Mining Journal*.

"Mr. Shreve has produced a work that must always take high rank as a text-book, * * * and no Bridge Engineer should be without it, as a valuable work of reference, and one that will frequently assist him out of difficulties."—*Franklin Institute Journal*.

The Kansas City Bridge.

4to. Cloth. \$6.00

WITH AN ACCOUNT OF THE REGIMEN OF THE MISSOURI RIVER, and a description of the Methods used for Founding in that River. By O. CHANUTE, Chief Engineer, and GEORGE MORISON, Assistant Engineer. Illustrated with five lithographic views and twelve plates of plans.

Illustrations.

VIEWS.—View of the Kansas City Bridge, August 2, 1869. Lowering Caisson No. 1 into position. Caisson for Pier No. 4 brought into position. View of Foundation Works, Pier No. 4. Pier No. 1.

PLATES.—I. Map showing location of Bridge. II. Water Record—Cross Section of River—Profile of Crossing—Pontoon Protection. III. Water Deadener—Caisson No. 2—Founda-

tion Works, Pier No. 3. IV. Foundation Works, Pier No. 4. V. Foundation Works, Pier No. 4. VI. Caisson No. 5—Sheet Piling at Pier No. 6—Details of Dredges—Pile Shoe—Betch Box. VII. Masonry—Draw Protection—False Works between Piers 3 and 4. VIII. Floating Derricks. IX. General Elevation—176 feet span. X. 248 feet span. XI. Plans of Draw. XII. Strain Diagrams.

Clarke's Quincy Bridge.

4to. Cloth. \$7.50.

DESCRIPTION OF THE IRON RAILWAY Bridge across the Mississippi River at Quincy, Illinois. By THOMAS CURTIS CLARKE, Chief Engineer. Illustrated with twenty-one lithographed plans.

Illustrations.

PLATES.—General Plan of Mississippi River at Quincy, showing location of Bridge. IIa. General Sections of Mississippi River at Quincy, showing location of Bridge. IIb. General Sections of Mississippi River at Quincy, showing location of Bridge. III. General Sections of Mississippi River at Quincy, showing location of Bridge. IV. Plans of Masonry. V. Diagram of Spans, showing the Dimensions, Arrangement of Panels, etc. VI. Two hundred and fifty feet span, and details. VII. Three hundred and sixty feet Pivot Draw. VIII. Details of three hundred and sixty feet Draw. IX. Ice-Breakers, Foundations of Piers and Abutments, Water Table, and

Curve of Deflections. X. Foundations of Pier 2, in Process of Construction. XI. Foundations of Pier 3, and its Protection. XII. Foundations of Pier 3, in Process of Construction, and Steam Dredge. XIII. Foundations of Piers 5 to 18, in Process of Construction. XIV. False Works, showing Process of Handling and Setting Stone. XV. False Works for Raising Iron Work of Superstructure. XVI. Steam Dredge used in Foundations 9 to 18. XVII. Single Bucket Dredge used in Foundations of Bay Piers. XVIII. Saws used for Cutting Piles under water. XIX. Sand Pump and Concrete Box. XX. Masonry Travelling Crane.

Whipple on Bridge Building.

8vo, Illustrated. Cloth. \$4.00.

AN ELEMENTARY AND PRACTICAL TREATISE ON BRIDGE BUILDING. An enlarged and improved edition of the Author's original work. By S. WHIPPLE, C. E., Inventor of the Whipple Bridges, &c. Second Edition.

The design has been to develop from Fundamental Principles a system easy of comprehension, and such as to enable the attentive reader and student to judge understandingly for himself, as to the relative merits of different plans and combinations, and to adopt for use such as may be most suitable for the cases he may have to deal with.

It is hoped the work may prove an appropriate Text-Book upon the subject treated of, for the Engineering Student, and a useful manual for the Practicing Engineer and Bridge Builder.

Stoney on Strains.

New and Revised Edition, with numerous illustrations.

Royal 8vo, 664 pp. Cloth. \$12.50.

THE THEORY OF STRAINS IN GIRDERS and Similar Structures, with Observations on the Application of Theory to Practice, and Tables of Strength and other Properties of Materials. By BINDON B. STONEY, B. A.

Roebling's Bridges.

Imperial folio. Cloth. \$25.00.

LONG AND SHORT SPAN RAILWAY BRIDGES. By JOHN A. ROEBLING, C. E. Illustrated with large copperplate engravings of plans and views.

List of Plates

1. Parabolic Truss Railway Bridge. 2, 3, 4, 5, 6. Details of Parabolic Truss, with centre span 500 feet in the clear. 7. Plan and View of a Bridge over the Mississippi River, at St. Louis, for railway and common travel. 8, 9, 10, 11, 12. Details and View of St. Louis Bridge. 13. Railroad Bridge over the Ohio.

Diedrichs' Theory of Strains.

8vo. Cloth. \$5.00.

A Compendium for the Calculation and Construction of Bridges, Roofs, and Cranes, with the Application of Trigonometrical Notes. Containing the most comprehensive information in regard to the Resulting Strains for a permanent Load, as also for a combined (Permanent and Rolling) Load. In two sections adapted to the requirements of the present time. By JOHN DIEDRICHS. Illustrated by numerous plates and diagrams.

"The want of a compact, universal and popular treatise on the Construction of Roofs and Bridges—especially one treating of the influence of a variable load—and the unsatisfactory essays of different authors on the subject, induced me to prepare this work."

Whilden's Strength of Materials.

12mo. Cloth. \$2.00.

ON THE STRENGTH OF MATERIALS used in Engineering Construction. By J. K. WHILDEN.

Campin on Iron Roofs.

Large 8vo. Cloth. \$2.00.

ON THE CONSTRUCTION OF IRON ROOFS. A Theoretical and Practical Treatise. By FRANCIS CAMPIN. With wood-cuts and plates of Roofs lately executed.

"The mathematical formulas are of an elementary kind, and the process admits of an easy extension so as to embrace the prominent varieties of iron truss bridges. The treatise, though of a practical scientific character, may be easily mastered by any one familiar with elementary mechanics and plane trigonometry."

Holley's Railway Practice.

1 vol. folio. Cloth. \$12.00.

AMERICAN AND EUROPEAN RAILWAY PRACTICE, in the Economical Generation of Steam, including the materials and construction of Coal-burning Boilers, Combustion, the Variable Blast, Vaporization, Circulation, Super-heating, Supplying and Heating Feed-water, &c., and the adaptation of Wood and Coke-burning Engines to Coal-burning; and in Permanent Way, including Road-bed, Sleepers, Rails, Joint Fastenings, Street Railways, &c., &c. By ALEXANDER L. HOLLEY, B. P. With 77 lithographed plates.

"This is an elaborate treatise by one of our ablest civil engineers, on the construction and use of locomotives, with a few chapters on the building of Railroads. * * * All these subjects are treated by the author, who is a first-class railroad engineer, in both an intelligent and intelligible manner. The facts and ideas are well arranged, and presented in a clear and simple style, accompanied by beautiful engravings, and we presume the work will be regarded as indispensable by all who are interested in a knowledge of the construction of railroads and rolling stock, or the working of locomotives."—*Scientific American*.

Henri's Skeleton Structures.

8vo. Cloth. \$1.50.

SKELETON STRUCTURES, especially in their Application to the building of Steel and Iron Bridges. By **OLAUS HENRIK**. With folding plates and diagrams.

By presenting these general examinations on Skeleton Structures, with particular application for Suspended Bridges, to Engineers, I venture to express the hope that they will receive these theoretical results with some confidence, even although an opportunity is wanting to compare them with practical results.

O. H.

Useful Information for Railway Men.

Pocket form. Morocco, gilt, \$2.00.

Compiled by **W. G. HAMILTON**, Engineer. Fifth edition, revised and enlarged. 570 pages.

"It embodies many valuable formulæ and recipes useful for railway men, and, indeed, for almost every class of persons in the world. The 'information' comprises some valuable formulæ and rules for the construction of boilers and engines, masonry, properties of steel and iron, and the strength of materials generally."—*Railroad Gazette, Chicago*.

Brooklyn Water Works.

1 vol. folio. Cloth. \$25.00.

A DESCRIPTIVE ACCOUNT OF THE CONSTRUCTION OF THE WORKS, and also Reports on the Brooklyn, Hartford, Belleville, and Cambridge Pumping Engines. Prepared and printed by order of the Board of Water Commissioners. With 59 illustrations.

CONTENTS.—Supply Ponds—The Conduit—Ridgewood Engine House and Pump Well—Ridgewood Engines—Force Mains—Ridgewood Reservoir—Pipe Distribution—Mount Prospect Reservoir—Mount Prospect Engine House and Engine—Drainage Grounds—Sewerage Works—Appendix.

Kirkwood on Filtration.

4to. Cloth. \$15.00.

REPORT ON THE FILTRATION OF RIVER WATERS, for the Supply of Cities, as practised in Europe, made to the Board of Water Commissioners of the City of St. Louis. By JAMES P. KIRKWOOD. Illustrated by 80 double-plate engravings.

CONTENTS.—Report on Filtration—London Works, General—Chelsea Water Works and Filters—Lambeth Water Works and Filters—Southwark and Vauxhall Water Works and Filters—Grand Junction Water Works and Filters—West Middlesex Water Works and Filters—New River Water Works and Filters—East London Water Works and Filters—Leicester Water Works and Filters—York Water Works and Filters—Liverpool Water Works and Filters—Edinburgh Water Works and Filters—Dublin Water Works and Filters—Perth Water Works and Filtering Gallery—Berlin Water Works and Filters—Hamburg Water Works and Reservoirs—Altona Water Works and Filters—Tours Water Works and Filtering Canal—Angers Water Works and Filtering Galleries—Nantes Water Works and Filters—Lyons Water Works and Filtering Galleries—Toulouse Water Works and Filtering Galleries—Marseilles Water Works and Filters—Genoa Water Works and Filtering Galleries—Leghorn Water Works and Cisterns—Wakefield Water Works and Filters—Appendix.

Tunner on Roll-Turning.

1 vol. 8vo. and 1 vol. plates. \$10.00.

A TREATISE ON ROLL-TURNING FOR THE MANUFACTURE OF IRON. By PETER TUNNER. Translated and adapted. By JOHN B. PEARSE, of the Pennsylvania Steel Works. With numerous wood-cuts, 8vo., together with a folio atlas of 10 lithographed plates of Rolls, Measurements, &c.

"We commend this book as a clear, elaborate, and practical treatise upon the department of iron manufacturing operations to which it is devoted. The writer states in his preface, that for twenty-five years he has felt the necessity of such a work, and has evidently brought to its preparation the fruits of experience, a painstaking regard for accuracy of statement, and a desire to furnish information in a style readily understood. The book should be in the hands of every one interested, either in the general practice of mechanical engineering, or the special branch of manufacturing operations to which the work relates."—*American Artisan*.

Glynn on the Power of Water.

12mo. Cloth. \$1.00.

A TREATISE ON THE POWER OF WATER, as applied to drive Flour Mills, and to give motion to Turbines and other Hydrostatic Engines. By JOSEPH GLYNN, F.R. S. Third edition, revised and enlarged, with numerous illustrations.

Hewson on Embankments.

8vo. Cloth. \$2.00.

PRINCIPLES AND PRACTICE OF EMBANKING LANDS from River Floods, as applied to the Levees of the Mississippi. By WILLIAM HEWSON, Civil Engineer.

"This is a valuable treatise on the principles and practice of embanking lands from river floods, as applied to the Levees of the Mississippi, by a highly intelligent and experienced engineer. The author says it is a first attempt to reduce to order and to rule the design, execution, and measurement of the Levees of the Mississippi. It is a most useful and needed contribution to scientific literature.—*Philadelphia Evening Journal*.

Grüner on Steel.

8vo. Cloth. \$3.50.

THE MANUFACTURE OF STEEL. By M. L. GRÜNER, translated from the French. By Lenox Smith, A. M., E. M., with an appendix on the Bessemer Process in the United States, by the translator. Illustrated by lithographed drawings and wood-cuts.

"The purpose of the work is to present a careful, elaborate, and at the same time practical examination into the physical properties of steel, as well as a description of the new processes and mechanical appliances for its manufacture. The information which it contains, gathered from many trustworthy sources, will be found of much value to the American steel manufacturer, who may thus acquaint himself with the results of careful and elaborate experiments in other countries, and better prepare himself for successful competition in this important industry with foreign makers. The fact that this volume is from the pen of one of the ablest metallurgists of the present day, cannot fail, we think, to secure for it a favorable consideration.—*Iron Age*.

Bauerman on Iron.

12mo. Cloth. \$2.00.

TREATISE ON THE METALLURGY OF IRON. Containing outlines of the History of Iron Manufacture, methods of Assay, and analysis of Iron Ores, processes of manufacture of Iron and Steel, etc., etc. By H. BAUERMAN. First American edition. Revised and enlarged, with an appendix on the Martin Process for making Steel, from the report of Abram S. Hewitt. Illustrated with numerous wood engravings.

"This is an important addition to the stock of technical works published in this country. It embodies the latest facts, discoveries, and processes connected with the manufacture of iron and steel, and should be in the hands of every person interested in the subject, as well as in all technical and scientific libraries."—*Scientific American*.

Link and Valve Motions, by W. S. Auchincloss.

8vo. Cloth. \$3.00.

APPLICATION OF THE SLIDE VALVE and Link Motion to Stationary, Portable, Locomotive and Marine Engines, with new and simple methods for proportioning the parts. By WILLIAM S. AUCHINCLOSS, Civil and Mechanical Engineer. Designed as a hand-book for Mechanical Engineers, Master Mechanics, Draughtsmen and Students of Steam Engineering. All dimensions of the valve are found with the greatest ease by means of a Printed Scale, and proportions of the link determined *without* the assistance of a model. Illustrated by 37 wood-cuts and 21 lithographic plates, together with a copperplate engraving of the Travel Scale.

All the matters we have mentioned are treated with a clearness and absence of unnecessary verbiage which renders the work a peculiarly valuable one. The Travel Scale only requires to be known to be appreciated. Mr. A. writes so ably on his subject, we wish he had written more. *London Engineering*.

We have never opened a work relating to steam which seemed to us better calculated to give an intelligent mind a clear understanding of the department it discusses.—*Scientific American*.

Slide Valve by Eccentrics, by Prof. C. W. MacCord.

4to. Illustrated. Cloth, \$4.00.

A PRACTICAL TREATISE ON THE SLIDE VALVE BY ECCENTRICS, examining by methods, the action of the Eccentric upon the Slide Valve, and explaining the practical processes of laying out the movements, adapting the valve for its various duties in the steam-engine. For the use of Engineers, Draughtsmen, Machinists, and Students of valve motions in general. By C. W. MACCORD, A. M., Professor of Mechanical Drawing, Stevens' Institute of Technology, Hoboken, N. J.

Stillman's Steam-Engine Indicator.

12mo. Cloth. \$1.00.

THE STEAM-ENGINE INDICATOR, and the Improved Manometer Steam and Vacuum Gauges; their utility and application By PAUL STILLMAN. New edition.

Bacon's Steam-Engine Indicator.

12mo. Cloth. \$1.00. Mor. \$1.50.

A TREATISE ON THE RICHARDS STEAM-ENGINE INDICATOR, with directions for its use. By CHARLES T. PORTER. Revised, with notes and large additions as developed by American Practice, with an Appendix containing useful formulæ and rules for Engineers. By F. W. BACON, M. E., Member of the American Society of Civil Engineers. Illustrated. Second Edition

In this work, Mr. Porter's book has been taken as the basis, but Mr. Bacon has adapted it to American Practice, and has conferred a great boon on American Engineers.—*Artisan*.

Bartol on Marine Boilers.

8vo. Cloth. \$1.50.

TREATISE ON THE MARINE BOILERS OF THE UNITED STATES. By H. B. BARTOL. Illustrated.

Gillmore's Limes and Cements.

Fourth Edition: Revised and Enlarged.

8vo. Cloth. \$4.00.

PRACTICAL TREATISE ON LIMES, HYDRAULIC CEMENTS, AND MORTARS. Papers on Practical Engineering, U. S. Engineer Department, No. 9, containing Reports of numerous experiments conducted in New York City, during the years 1858 to 1861, inclusive. By Q. A. GILLMORE, Brig-General U. S. Volunteers, and Major U. S. Corps of Engineers. With numerous illustrations.

"This work contains a record of certain experiments and researches made under the authority of the Engineer Bureau of the War Department from 1858 to 1861, upon the various hydraulic cements of the United States, and the materials for their manufacture. The experiments were carefully made, and are well reported and compiled."—*Journal Franklin Institute.*

Gillmore's Coignet Beton.

8vo. Cloth. \$2.50.

COIGNET BETON AND OTHER ARTIFICIAL STONE. By Q. A. GILLMORE. 9 Plates, Views, etc.

This work describes with considerable minuteness of detail the several kinds of artificial stone in most general use in Europe and now beginning to be introduced in the United States, discusses their properties, relative merits, and cost, and describes the materials of which they are composed. . . . The subject is one of special and growing interest, and we commend the work, embodying as it does the matured opinions of an experienced engineer and expert.

Williamson's Practical Tables.

4to. Flexible Cloth. \$2.50.

PRACTICAL TABLES IN METEOROLOGY AND HYPSONOMETRY, in connection with the use of the Barometer. By Col. R. S. WILLIAMSON, U. S. A.

Williamson on the Barometer.

4to. Cloth. \$15.00.

ON THE USE OF THE BAROMETER ON SURVEYS AND RECONNAISSANCES. Part I. Meteorology in its Connection with Hypsometry. Part II. Barometric Hypsometry. By R. S. WILLIAMSON, Bvt. Lieut.-Col. U. S. A., Major Corps of Engineers. With Illustrative Tables and Engravings. Paper No. 15, Professional Papers, Corps of Engineers.

"SAN FRANCISCO, CAL., Feb. 27, 1867.

"Gen. A. A. HUMPHREYS, Chief of Engineers, U. S. Army:

"GENERAL,—I have the honor to submit to you, in the following pages, the results of my investigations in meteorology and hypsometry, made with the view of ascertaining how far the barometer can be used as a reliable instrument for determining altitudes on extended lines of survey and reconnoissances. These investigations have occupied the leisure permitted me from my professional duties during the last ten years, and I hope the results will be deemed of sufficient value to have a place assigned them among the printed professional papers of the United States Corps of Engineers.

"Very respectfully, your obedient servant,

"R. S. WILLIAMSON,

"Bvt. Lt.-Col. U. S. A., Major Corps of U. S. Engineers."

Von Cotta's Ore Deposits.

8vo. Cloth. \$4.00.

TREATISE ON ORE DEPOSITS. By BERNHARD VON COTTA, Professor of Geology in the Royal School of Mines, Freiberg, Saxony. Translated from the second German edition, by FREDERICK PRIME, Jr., Mining Engineer, and revised by the author, with numerous illustrations.

"Prof. Von Cotta of the Freiberg School of Mines, is the author of the best modern treatise on ore deposits, and we are heartily glad that this admirable work has been translated and published in this country. The translator, Mr. Frederick Prime, Jr., a graduate of Freiberg, has had in his work the great advantage of a revision by the author himself, who declares in a prefatory note that this may be considered as a new edition (the third, of his own book.

"It is a timely and welcome contribution to the literature of mining in this country, and we are grateful to the translator for his enterprise and good judgment in undertaking its preparation; while we recognize with equal cordiality the liberality of the author in granting both permission and assistance."—*Extract from Review in Engineering and Mining Journal.*

Plattner's Blow-Pipe Analysis.

Second edition. Revised. 8vo. Cloth. \$7.50.

PLATTNER'S MANUAL OF QUALITATIVE AND QUANTITATIVE ANALYSIS WITH THE BLOW-PIPE. From the last German edition Revised and enlarged. By Prof. TH. RICHTER, of the Royal Saxon Mining Academy. Translated by Prof. H. B. CORNWALL, Assistant in the Columbia School of Mines, New York; assisted by JOHN H. CASWELL. Illustrated with eighty-seven wood-cuts and one Lithographic Plate. 560 pages.

"Plattner's celebrated work has long been recognized as the only complete book on Blow-Pipe Analysis. The fourth German edition, edited by Prof. Richter, fully sustains the reputation which the earlier editions acquired during the lifetime of the author, and it is a source of great satisfaction to us to know that Prof. Richter has co-operated with the translator in issuing the American edition of the work, which is in fact a fifth edition of the original work, being far more complete than the last German edition."—*Silliman's Journal*.

There is nothing so complete to be found in the English language. Plattner's book is not a mere pocket edition; it is intended as a comprehensive guide to all that is at present known on the blow-pipe, and as such is really indispensable to teachers and advanced pupils.

"Mr. Cornwall's edition is something more than a translation, as it contains many corrections, emendations and additions not to be found in the original. It is a decided improvement on the work in its German dress."—*Journal of Applied Chemistry*.

Egleston's Mineralogy.

8vo. Illustrated with 84 Lithographic Plates. Cloth. \$4.50.

LECTURES ON DESCRIPTIVE MINERALOGY, Delivered at the School of Mines, Columbia College. BY PROFESSOR T. EGLESTON.

These lectures are what their title indicates, the lectures on Mineralogy delivered at the School of Mines of Columbia College. They have been printed for the students, in order that more time might be given to the various methods of examining and determining minerals. The second part has only been printed. The first part, comprising crystallography and physical mineralogy, will be printed at some future time.

Pynchon's Chemical Physics.

New Edition. Revised and Enlarged.

Crown 8vo. Cloth. \$3.00.

INTRODUCTION TO CHEMICAL PHYSICS, Designed for the Use of Academies, Colleges, and High Schools. Illustrated with numerous engravings, and containing copious experiments with directions for preparing them. By THOMAS RUGGLES PYNCHON, M.A., Professor of Chemistry and the Natural Sciences, Trinity College, Hartford.

Hitherto, no work suitable for general use, treating of all these subjects within the limits of a single volume, could be found; consequently the attention they have received has not been at all proportionate to their importance. It is believed that a book containing so much valuable information within so small a compass, cannot fail to meet with a ready sale among all intelligent persons, while Professional men, Physicians, Medical Students, Photographers, Telegraphers, Engineers, and Artisans generally, will find it specially valuable, if not nearly indispensable, as a book of reference.

"We strongly recommend this able treatise to our readers as the first work ever published on the subject free from perplexing technicalities. In style it is pure, in description graphic, and its typographical appearance is artistic. It is altogether a most excellent work."—*Eclectic Medical Journal*.

"It treats fully of Photography, Telegraphy, Steam Engines, and the various applications of Electricity. In short, it is a carefully prepared volume, abreast with the latest scientific discoveries and inventions."—*Hartford Courant*.

Plympton's Blow-Pipe Analysis.

12mo. Cloth. \$2.00.

THE BLOW-PIPE: A System of Instruction in its practical use being a graduated course of Analysis for the use of students, and all those engaged in the Examination of Metallic Combinations. Second edition, with an appendix and a copious index. By GEORGE W. PLYMPTON, of the Polytechnic Institute, Brooklyn.

"This manual probably has no superior in the English language as a textbook for beginners, or as a guide to the student working without a teacher. To the latter many illustrations of the utensils and apparatus required in using the blow-pipe, as well as the fully illustrated description of the blow-pipe flame, will be especially serviceable."—*New York Teacher*.

Ure's Dictionary.

Sixth Edition.

London, 1872.

3 vols. 8vo. Cloth, \$25.00. Half Russia, \$32.50.

DICTIONARY OF ARTS, MANUFACTURES, AND MINES.

By ANDREW URE, M.D. Sixth edition. Edited by ROBERT HUNT, F.R.S., greatly enlarged and rewritten.

Brande and Cox's Dictionary.

New Edition.

London, 1872.

3 vols. 8vo. Cloth, \$20.00. Half Morocco, \$27.50.

A Dictionary of Science, Literature, and Art. Edited by W. T. BRANDE and Rev. Geo. W. Cox. New and enlarged edition.

Watt's Dictionary of Chemistry.

Supplementary Volume.

8vo. Cloth. \$9.00.

This volume brings the Record of Chemical Discovery down to the end of the year 1869, including also several additions to, and corrections of, former results which have appeared in 1870 and 1871.

* * Complete Sets of the Work, New and Revised edition, including above supplement. 6 vols. 8vo. Cloth. \$62.00.

Rammelsberg's Chemical Analysis.

8vo. Cloth. \$2.25.

GUIDE TO A COURSE OF QUANTITATIVE CHEMICAL ANALYSIS, ESPECIALLY OF MINERALS AND FURNACE PRODUCTS. Illustrated by Examples. By C. F. RAMMELSBERG. Translated by J. TOWLER, M.D.

This work has been translated, and is now published expressly for those students in chemistry whose time and other studies in colleges do not permit them to enter upon the more elaborate and expensive treatises of Fresenius and others. It is the condensed labor of a master in chemistry and of a practical analyst.

Eliot and Storer's Qualitative Chemical Analysis.

New Edition, Revised.

12mo. Illustrated. Cloth. \$1.50.

A COMPENDIOUS MANUAL OF QUALITATIVE CHEMICAL ANALYSIS. By CHARLES W. ELIOT and FRANK H. STORER. Revised with the Coöperation of the Authors, by WILLIAM RIPLEY NICHOLS, Professor of Chemistry in the Massachusetts Institute of Technology.

"This Manual has great merits as a practical introduction to the science and the art of which it treats. It contains enough of the theory and practice of qualitative analysis, "in the wet way," to bring out all the reasoning involved in the science, and to present clearly to the student the most approved methods of the art. It is specially adapted for exercises and experiments in the laboratory; and yet its classifications and manner of treatment are so systematic and logical throughout, as to adapt it in a high degree to that higher class of students generally who desire an accurate knowledge of the practical methods of arriving at scientific facts."—*Lutheran Observer*.

"We wish every academical class in the land could have the benefit of the fifty exercises of two hours each necessary to master this book. Chemistry would cease to be a mere matter of memory, and become a pleasant experimental and intellectual recreation. We heartily commend this little volume to the notice of those teachers who believe in using the sciences as means of mental discipline."—*College Courier*.

Craig's Decimal System.

Square 82mo. Limp. 50c.

WEIGHTS AND MEASURES. An Account of the Decimal System, with Tables of Conversion for Commercial and Scientific Uses. By B. F. CRAIG, M. D.

"The most lucid, accurate, and useful of all the hand-books on this subject that we have yet seen. It gives forty-seven tables of comparison between the English and French denominations of length, area, capacity, weight, and the Centigrade and Fahrenheit thermometers, with clear instructions how to use them; and to this practical portion, which helps to make the transition as easy as possible, is prefixed a scientific explanation of the errors in the metric system, and how they may be corrected in the laboratory."—*Nation*.

Nugent on Optics.

12mo. Cloth. \$2.00

TREATISE ON OPTICS; or, Light and Sight, theoretically and practically treated; with the application to Fine Art and Industrial Pursuits. By E. NUGENT. With one hundred and three illustrations.

"This book is of a practical rather than a theoretical kind, and is designed to afford accurate and complete information to all interested in applications of the science."—*Round Table*.

Barnard's Metric System.

8vo. Brown cloth. \$3.00.

THE METRIC SYSTEM OF WEIGHTS AND MEASURES.

An Address delivered before the Convocation of the University of the State of New York, at Albany, August, 1871. By FREDERICK A. P. BARNARD, President of Columbia College, New York City. Second edition from the Revised edition printed for the Trustees of Columbia College. Tinted paper.

"It is the best summary of the arguments in favor of the metric weights and measures with which we are acquainted, not only because it contains in small space the leading facts of the case, but because it puts the advocacy of that system on the only tenable grounds, namely, the great convenience of a decimal notation of weight and measure as well as money, the value of international uniformity in the matter, and the fact that this metric system is adopted and in general use by the majority of civilized nations."—*The Nation*.

The Young Mechanic.

Illustrated. 12mo. Cloth. \$1.75.

THE YOUNG MECHANIC. Containing directions for the use of all kinds of tools, and for the construction of steam engines and mechanical models, including the Art of Turning in Wood and Metal. By the author of "The Lathe and its Uses," etc. From the English edition, with corrections.

Harrison's Mechanic's Tool-Book.

12mo. Cloth. \$1.50.

MECHANIC'S TOOL BOOK, with practical rules and suggestions, for the use of Machinists, Iron Workers, and others. By W. B. HARRISON, Associate Editor of the "American Artisan." Illustrated with 44 engravings.

"This work is specially adapted to meet the wants of Machinists and workers in iron generally. It is made up of the work-day experience of an intelligent and ingenious mechanic, who had the faculty of adapting tools to various purposes. The practicability of his plans and suggestions are made apparent even to the unpractised eye by a series of well-executed wood engravings."—*Philadelphia Inquirer*.

Pope's Modern Practice of the Electric Telegraph.

Eighth Edition. 8vo. Cloth \$2.00.

A Hand-book for Electricians and Operators. By FRANK L. POPE. Seventh edition. Revised and enlarged, and fully illustrated.

Extract from Letter of Prof. Morse.

"I have had time only cursorily to examine its contents, but this examination has resulted in great gratification, especially at the fairness and unprejudiced tone of your whole work.

"Your illustrated diagrams are admirable and beautifully executed.

"I think all your instructions in the use of the telegraph apparatus judicious and correct, and I most cordially wish you success."

Extract from Letter of Prof. G. W. Hough, of the Dudley Observatory.

"There is no other work of this kind in the English language that contains in so small a compass so much practical information in the application of galvanic electricity to telegraphy. It should be in the hands of every one interested in telegraphy, or the use of Batteries for other purposes."

Morse's Telegraphic Apparatus.

Illustrated. 8vo. Cloth. \$2.00.

EXAMINATION OF THE TELEGRAPHIC APPARATUS AND THE PROCESSES IN TELEGRAPHY. By SAMUEL F. B. MORSE, LL.D., United States Commissioner Paris Universal Exposition, 1867.

Sabine's History of the Telegraph.

12mo. Cloth. \$1.25.

HISTORY AND PROGRESS OF THE ELECTRIC TELEGRAPH, with Descriptions of some of the Apparatus. By ROBERT SABINE, C. E. Second edition, with additions.

CONTENTS.—I. Early Observations of Electrical Phenomena. II. Telegraphs by Frictional Electricity. III. Telegraphs by Voltaic Electricity. IV. Telegraphs by Electro-Magnetism and Magneto-Electricity. V. Telegraphs now in use. VI. Overhead Lines. VII. Submarine Telegraph Lines. VIII. Underground Telegraphs. IX. Atmospheric Electricity.

Haskins' Galvanometer.

Pocket form. Illustrated. Morocco tucks. \$2.00.

THE GALVANOMETER, AND ITS USES; a Manual for Electricians and Students. By C. H. HASKINS.

"We hope this excellent little work will meet with the sale its merits entitle it to. To every telegrapher who owns, or uses a Galvanometer, or ever expects to, it will be quite indispensable."—*The Telegrapher*.

Culley's Hand-Book of Telegraphy.

8vo. Cloth. \$2.00.

A HAND-BOOK OF PRACTICAL TELEGRAPHY. By R. S. CULLEY, Engineer to the Electric and International Telegraph Company. Fifth edition, revised and enlarged.

Foster's Submarine Blasting.

4to. Cloth. \$3.50.

SUBMARINE BLASTING in Boston Harbor, Massachusetts—Removal of Tower and Corwin Rocks. By JOHN G. FOSTER, Lieutenant-Colonel of Engineers, and Brevet Major-General, U. S. Army. Illustrated with seven plates.

LIST OF PLATES.—1. Sketch of the Narrows, Boston Harbor. 2. Townsend's Submarine Drilling Machine, and Working Vessel attending. 3. Submarine Drilling Machine employed. 4. Details of Drilling Machine employed. 5. Cartridges and Tamping used. 6. Fuses and Insulated Wires used. 7. Portable Friction Battery used.

Barnes' Submarine Warfare.

8vo. Cloth. \$5.00.

SUBMARINE WARFARE, DEFENSIVE AND OFFENSIVE.

Comprising a full and complete History of the Invention of the Torpedo, its employment in War and results of its use. Descriptions of the various forms of Torpedoes, Submarine Batteries and Torpedo Boats actually used in War. Methods of Ignition by Machinery, Contact Fuzes, and Electricity, and a full account of experiments made to determine the Explosive Force of Gunpowder under Water. Also a discussion of the Offensive Torpedo system, its effect upon Iron-Clad Ship systems, and influence upon Future Naval Wars. By Lieut.-Commander JOHN S. BARNES, U. S. N. With twenty lithographic plates and many wood-cuts.

"A book important to military men, and especially so to engineers and artillerymen. It consists of an examination of the various offensive and defensive engines that have been contrived for submarine hostilities, including a discussion of the torpedo system, its effects upon iron-clad ship systems, and its probable influence upon future naval wars. Plates of a valuable character accompany the treatise, which affords a useful history of the momentous subject it discusses. A great deal of useful information is collected in its pages, especially concerning the inventions of SCROLL and VERBU, and of JONES' and HUNT's batteries, as well as of other similar machines, and the use in submarine operations of gun-cotton and nitro-glycerine."—*N. Y. Times*.

Randall's Quartz Operator's Hand-Book.

12mo. Cloth. \$2.00.

QUARTZ OPERATOR'S HAND-BOOK. By P. M. RANDALL.

New edition, revised and enlarged. Fully illustrated.

The object of this work has been to present a clear and comprehensive exposition of mineral veins, and the means and modes chiefly employed for the mining and working of their ores—more especially those containing gold and silver.

Mitchell's Manual of Assaying.

8vo. Cloth. \$10.00.

A MANUAL OF PRACTICAL ASSAYING. By JOHN MITCHELL.
Third edition. Edited by WILLIAM CROOKES, F.R.S.

In this edition are incorporated all the late important discoveries in Assaying made in this country and abroad, and special care is devoted to the very important Volumetric and Colorimetric Assays, as well as to the Blow-Pipe Assays.

Benét's Chronoscope.

Second Edition.

Illustrated. 4to. Cloth. \$3.00.

ELECTRO-BALLISTIC MACHINES, and the Schultz Chronoscope. By Lieutenant-Colonel S. V. BENÉT, Captain of Ordnance, U. S. Army.

CONTENTS.—1. Ballistic Pendulum. 2. Gun Pendulum. 3. Use of Electricity. 4. Navez' Machine. 5. Vignotti's Machine, with Plates. 6. Benton's Electro-Ballistic Pendulum, with Plates. 7. Leur's Tro-Pendulum Machine. 8. Schultz's Chronoscope, with two Plates.

Michaelis' Chronograph.

4to. Illustrated. Cloth. \$3.00.

THE LE BOULENGÉ CHRONOGRAPH. With three lithographed folding plates of illustrations. By Brevet Captain O E. MICHAELIS, First Lieutenant Ordnance Corps, U. S. Army.

"The excellent monograph of Captain Michaelis enters minutely into the details of construction and management, and gives tables of the times of flight calculated upon a given fall of the chronometer for all distances. Captain Michaelis has done good service in presenting this work to his brother officers, describing, as it does, an instrument which bids fair to be in constant use in our future ballistic experiments."—*Army and Navy Journal*.

Silversmith's Hand-Book.

Fourth Edition.

Illustrated. 12mo. Cloth. \$3.00.

A PRACTICAL HAND-BOOK FOR MINERS, Metallurgists, and Assayers, comprising the most recent improvements in the disintegration, amalgamation, smelting, and parting of the Precious Ores, with a Comprehensive Digest of the Mining Laws. Greatly augmented, revised, and corrected. By JULIUS SILVERSMITH. Fourth edition. Profusely illustrated. 1 vol. 12mo. Cloth. \$3.00.

One of the most important features of this work is that in which the metallurgy of the precious metals is treated of. In it the author has endeavored to embody all the processes for the reduction and manipulation of the precious ores heretofore successfully employed in Germany, England, Mexico, and the United States, together with such as have been more recently invented, and not yet fully tested—all of which are profusely illustrated and easy of comprehension.

Simms' Levelling.

8vo. Cloth. \$2.50.

A TREATISE ON THE PRINCIPLES AND PRACTICE OF LEVELLING, showing its application to purposes of Railway Engineering and the Construction of Roads, &c. By FREDERICK W. SIMMS, C. E. From the fifth London edition, revised and corrected, with the addition of Mr. Law's Practical Examples for Setting Out Railway Curves. Illustrated with three lithographic plates and numerous wood-cuts.

"One of the most important text-books for the general surveyor, and there is scarcely a question connected with levelling for which a solution would be sought, but that would be satisfactorily answered by consulting this volume."
—*Mining Journal*.

"The text-book on levelling in most of our engineering schools and colleges."—*Engineers*.

"The publishers have rendered a substantial service to the profession, especially to the younger members, by bringing out the present edition of Mr. Simms useful work."—*Engineering*.

Stuart's Successful Engineer.

18mo. Boards. 50 cents.

HOW TO BECOME A SUCCESSFUL ENGINEER: Being Hints to Youths intending to adopt the Profession. By BERNARD STUART, Engineer. Sixth Edition.

"A valuable little book of sound, sensible advice to young men who wish to rise in the most important of the professions."—*Scientific American*.

Stuart's Naval Dry Docks.

Twenty-four engravings on steel.

Fourth Edition.

4to. Cloth. \$6.00.

THE NAVAL DRY DOCKS OF THE UNITED STATES.

By CHARLES B. STUART. Engineer in Chief of the United States Navy.

List of Illustrations.

Pumping Engine and Pumps—Plan of Dry Dock and Pump-Well—Sections of Dry Dock—Engine House—Iron Floating Gate—Details of Floating Gate—Iron Turning Gate—Plan of Turning Gate—Culvert Gate—Filling Culvert Gates—Engine Bed—Plate, Pumps, and Culvert—Engine House Roof—Floating Sectional Dock—Details of Section, and Plan of Turn-Tables—Plan of Basin and Marine Railways—Plan of Sliding Frame, and Elevation of Pumps—Hydraulic Cylinder—Plan of Gearing for Pumps and End Floats—Perspective View of Dock, Basin, and Railway—Plan of Basin of Portsmouth Dry Dock—Floating Balance Dock—Elevation of Trusses and the Machinery—Perspective View of Balance Dry Dock

Free Hand Drawing.

Profusely Illustrated. 18mo. Boards. 50 cents.

A GUIDE TO ORNAMENTAL, Figure, and Landscape Drawing. By an Art Student.

CONTENTS.—Materials employed in Drawing, and how to use them—On Lines and how to Draw them—On Shading—Concerning lines and shading, with applications of them to simple elementary subjects—Sketches from Nature.

Minifie's Mechanical Drawing.

Eighth Edition.

Royal 8vo. Cloth. \$4.00.

A TEXT-BOOK OF GEOMETRICAL DRAWING for the use of Mechanics and Schools, in which the Definitions and Rules of Geometry are familiarly explained; the Practical Problems are arranged, from the most simple to the more complex, and in their description technicalities are avoided as much as possible. With illustrations for Drawing Plans, Sections, and Elevations of Buildings and Machinery; an Introduction to Isometrical Drawing, and an Essay on Linear Perspective and Shadows. Illustrated with over 200 diagrams engraved on steel. By WM. MINIFIE, Architect. Eighth Edition. With an Appendix on the Theory and Application of Colors.

"It is the best work on Drawing that we have ever seen, and is especially a text-book of Geometrical Drawing for the use of Mechanics and Schools. No young Mechanic, such as a Machinist, Engineer, Cabinet-Maker, Millwright, or Carpenter, should be without it."—*Scientific American*.

"One of the most comprehensive works of the kind ever published, and cannot but possess great value to builders. The style is at once elegant and substantial."—*Pennsylvania Inquirer*.

"Whatever is said is rendered perfectly intelligible by remarkably well-executed diagrams on steel, leaving nothing for mere vague supposition; and the addition of an introduction to isometrical drawing, linear perspective, and the projection of shadows, winding up with a useful index to technical terms."—*Glasgow Mechanics' Journal*.

☞ The British Government has authorized the use of this book in their schools of art at Somerset House, London, and throughout the kingdom.

Minifie's Geometrical Drawing.

New Edition. Enlarged.

12mo. Cloth. \$2.00.

GEOMETRICAL DRAWING. Abridged from the octavo edition, for the use of Schools. Illustrated with 48 steel plates. New edition, enlarged.

"It is well adapted as a text-book of drawing to be used in our High Schools and Academies where this useful branch of the fine arts has been hitherto too much neglected."—*Boston Journal*.

Bell on Iron Smelting.

8vo. Cloth. \$6.00.

CHEMICAL PHENOMENA OF IRON SMELTING. An experimental and practical examination of the circumstances which determine the capacity of the Blast Furnace, the Temperature of the Air, and the Proper Condition of the Materials to be operated upon. By I. LOWTHIAN BELL.

"The reactions which take place in every foot of the blast-furnace have been investigated, and the nature of every step in the process, from the introduction of the raw material into the furnace to the production of the pig iron, has been carefully ascertained, and recorded so fully, that any one in the trade can readily avail themselves of the knowledge acquired; and we have no hesitation in saying that the judicious application of such knowledge will do much to facilitate the introduction of arrangements which will still further economize fuel, and at the same time permit of the quality of the resulting metal being maintained, if not improved. The volume is one which no practical pig iron manufacturer can afford to be without if he be desirous of entering upon that competition which nowadays is essential to progress, and in issuing such a work Mr. Bell has entitled himself to the best thanks of every member of the trade."—*London Mining Journal*.

King's Notes on Steam.

Thirteenth Edition.

8vo. Cloth. \$2.00.

LESSONS AND PRACTICAL NOTES ON STEAM, the Steam-Engine, Propellers, &c., &c., for Young Engineers, Students, and others. By the late W. R. KING, U. S. N. Revised by Chief-Engineer J. W. KING, U. S. Navy.

"This is one of the best, because eminently plain and practical treatises on the Steam Engine ever published."—*Philadelphia Press*.

This is the thirteenth edition of a valuable work of the late W. H. King, U. S. N. It contains lessons and practical notes on Steam and the Steam Engine, Propellers, etc. It is calculated to be of great use to young marine engineers, students, and others. The text is illustrated and explained by numerous diagrams and representations of machinery.—*Boston Daily Advertiser*.

Text-book at the U. S. Naval Academy, Annapolis.

Burgh's Modern Marine Engineering.

One thick 4to vol. Cloth. \$25.00. Half morocco. \$30.00.

MODERN MARINE ENGINEERING, applied to Paddle and Screw Propulsion. Consisting of 36 Colored Plates, 259 Practical Wood-cut Illustrations, and 403 pages of Descriptive Matter, the whole being an exposition of the present practice of the following firms: Messrs. J. Penn & Sons; Messrs. Maudslay, Sons & Field; Messrs. James Watt & Co.; Messrs. J. & G. Rennie; Messrs. R. Napier & Sons; Messrs. J. & W. Dudgeon; Messrs. Ravenhill & Hodgson; Messrs. Humphreys & Tenant; Mr. J. T. Spencer, and Messrs. Forrester & Co. By N. P. BURGH, Engineer.

PRINCIPAL CONTENTS.—General Arrangements of Engines, 11 examples—General Arrangement of Boilers, 14 examples—General Arrangement of Superheaters, 11 examples—Details of Oscillating Paddle Engines, 34 examples—Condensers for Screw Engines, both Injection and Surface, 20 examples—Details of Screw Engines, 20 examples—Cylinders and Details of Screw Engines, 21 examples—Slide Valves and Details, 7 examples—Slide Valve, Link Motion, 7 examples—Expansion Valves and Gear, 10 examples—Details in General, 30 examples—Screw Propeller and Fittings, 13 examples—Engine and Boiler Fittings, 28 examples—In relation to the Principles of the Marine Engine and Boiler, 33 examples.

Notices of the Press.

"Every conceivable detail of the Marine Engine, under all its various forms, is profusely, and we must add, admirably illustrated by a multitude of engravings, selected from the best and most modern practice of the first Marine Engineers of the day. The chapter on Condensers is peculiarly valuable. In one word, there is no other work in existence which will bear a moment's comparison with it as an exponent of the skill, talent and practical experience to which is due the splendid reputation enjoyed by many British Marine Engineers." - *Engineer*.

"This very comprehensive work, which was issued in Monthly parts, has just been completed. It contains large and full drawings and copious descriptions of most of the best examples of Modern Marine Engines, and it is a complete theoretical and practical treatise on the subject of Marine Engineering." - *American Artisan*.

This is the only edition of the above work with the beautifully colored plates, and it is out of print in England.

Bourne's Treatise on the Steam Engine.

Ninth Edition.

Illustrated. 4to. Cloth. \$15.00.

TREATISE ON THE STEAM ENGINE in its various applications to Mines, Mills, Steam Navigation, Railways, and Agriculture, with the theoretical investigations respecting the Motive Power of Heat and the proper Proportions of Steam Engines. Elaborate Tables of the right dimensions of every part, and Practical Instructions for the Manufacture and Management of every species of Engine in actual use. By JOHN BOURNE, being the ninth edition of "A Treatise on the Steam Engine," by the "Artisan Club." Illustrated by thirty-eight plates and five hundred and forty-six wood-cuts.

As Mr. Bourne's work has the great merit of avoiding unsound and immature views, it may safely be consulted by all who are really desirous of acquiring trustworthy information on the subject of which it treats. During the twenty-two years which have elapsed from the issue of the first edition, the improvements introduced in the construction of the steam engine have been both numerous and important, and of these Mr. Bourne has taken care to point out the more prominent, and to furnish the reader with such information as shall enable him readily to judge of their relative value. This edition has been thoroughly modernized, and made to accord with the opinions and practice of the more successful engineers of the present day. All that the book professes to give is given with ability and evident care. The scientific principles which are permanent are admirably explained, and reference is made to many of the more valuable of the recently introduced engines. To express an opinion of the value and utility of such a work as *The Artisan Club's Treatise on the Steam Engine*, which has passed through eight editions already, would be superfluous; but it may be safely stated that the work is worthy the attentive study of all either engaged in the manufacture of steam engines or interested in economizing the use of steam.—*Mining Journal*.

Isherwood's Engineering Precedents.

Two Vols. in One. 8vo. Cloth. \$2.50.

ENGINEERING PRECEDENTS FOR STEAM MACHINERY.

Arranged in the most practical and useful manner for Engineers. By B. F. ISHERWOOD, Civil Engineer, U. S. Navy. With illustrations.

Ward's Steam for the Million.

New and Revised Edition.

8vo. Cloth. \$1.00.

STEAM FOR THE MILLION. A Popular Treatise on Steam and its Application to the Useful Arts, especially to Navigation. By J. H. WARD, Commander U. S. Navy. New and revised edition.

A most excellent work for the young engineer and general reader. Many facts relating to the management of the boiler and engine are set forth with a simplicity of language and perfection of detail that bring the subject home to the reader.—*American Engineer.*

Walker's Screw Propulsion.

8vo. Cloth. 75 cents.

NOTES ON SCREW PROPULSION, its Rise and History. By Capt. W. H. WALKER, U. S. Navy.

Commander Walker's book contains an immense amount of concise practical data, and every item of information recorded fully proves that the various points bearing upon it have been well considered previously to expressing an opinion.—*London Mining Journal.*

Page's Earth's Crust.

18mo. Cloth. 75 cents.

THE EARTH'S CRUST: a Handy Outline of Geology. By DAVID PAGE.

"Such a work as this was much wanted—a work giving in clear and intelligible outline the leading facts of the science, without amplification or irksome details. It is admirable in arrangement, and clear and easy, and, at the same time, forcible in style. It will lead, we hope, to the introduction of Geology into many schools that have neither time nor room for the study of large treatises."—*The J. useum.*

Rogers' Geology of Pennsylvania.

3 Vols. 4to, with Portfolio of Maps. Cloth. \$30.00.

THE GEOLOGY OF PENNSYLVANIA. A Government Survey. With a general view of the Geology of the United States, Essays on the Coal Formation and its Fossils, and a description of the Coal Fields of North America and Great Britain. By HENRY DARWIN ROGERS, Late State Geologist of Pennsylvania. Splendidly illustrated with Plates and Engravings in the Text.

It certainly should be in every public library throughout the country, and likewise in the possession of all students of Geology. After the final sale of these copies, the work will, of course, become more valuable.

The work for the last five years has been entirely out of the market, but a few copies that remained in the hands of Prof. Rogers, in Scotland, at the time of his death, are now offered to the public, at a price which is even below what it was originally sold for when first published.

Morfit on Pure Fertilizers.

With 28 Illustrative Plates. 8vo. Cloth. \$20.00.

A PRACTICAL TREATISE ON PURE FERTILIZERS, and the Chemical Conversion of Rock Guanos, Marlstones, Coprolites, and the Crude Phosphates of Lime and Alumina Generally, into various Valuable Products. By CAMPBELL MORFIT, M.D., F.C.S.

Sweet's Report on Coal.

8vo. Cloth. \$3.00.

SPECIAL REPORT ON COAL; showing its Distribution, Classification, and Cost delivered over different routes to various points in the State of New York, and the principal cities on the Atlantic Coast. By S. H. SWEET. With maps.

Colburn's Gas Works of London.

12mo. Boards. 60 cents.

GAS WORKS OF LONDON. By ZERAH COLBURN.

The Useful Metals and their Alloys; Scoffren, Truran, and others.

Fifth Edition.

8vo. Half calf. \$3.75.

THE USEFUL METALS AND THEIR ALLOYS, including MINING VENTILATION, MINING JURISPRUDENCE AND METALLURGIC CHEMISTRY employed in the conversion of IRON, COPPER, TIN, ZINC, ANTIMONY, AND LEAD ORES, with their applications to THE INDUSTRIAL ARTS. By JOHN SCOFFREN, WILLIAM TURAN, WILLIAM CLAY, ROBERT OXLAND, WILLIAM FAIRBAIRN, W. C. AITKIN, and WILLIAM VOSE PICKETT.

Collins' Useful Alloys.

18mo. Flexible. 75 cents.

THE PRIVATE BOOK OF USEFUL ALLOYS and Memoranda for Goldsmiths, Jewellers, etc. By JAMES E. COLLINS

This little book is compiled from notes made by the Author from the papers of one of the largest and most eminent Manufacturing Goldsmiths and Jewellers in this country, and as the firm is now no longer in existence, and the Author is at present engaged in some other undertaking, he now offers to the public the benefit of his experience, and in so doing he begs to state that all the alloys, etc., given in these pages may be confidently relied on as being thoroughly practicable.

The Memoranda and Receipts throughout this book are also compiled from practice, and will no doubt be found useful to the practical jeweller. —*Shirley, July, 1871.*

Joynton's Metals Used in Construction.

12mo. Cloth. 75 cents.

THE METALS USED IN CONSTRUCTION: Iron, Steel, Bessemer Metal, etc., etc. By FRANCIS HERBERT JOYNTON. Illustrated.

"In the interests of practical science, we are bound to notice this work; and to those who wish further information, we should say, buy it; and the outlay, we honestly believe, will be considered well spent." —*Scientific Review.*

Holley's Ordnance and Armor.

493 Engravings. Half Roan, \$10.00. Half Russia, \$12.00.

A TREATISE ON ORDNANCE AND ARMOR—Embracing Descriptions, Discussions, and Professional Opinions concerning the MATERIAL, FABRICATION, Requirements, Capabilities, and Endurance of European and American Guns, for Naval, Sea Coast, and Iron-clad Warfare, and their RIFLING, PROJECTILES, and BREECH-LOADING; also, Results of Experiments against Armor, from Official Records, with an Appendix referring to Gun-Cotton, Hooped Guns, etc., etc. By ALEXANDER L. HOLLEY, B. P. 948 pages, 493 Engravings, and 147 Tables of Results, etc.

CONTENTS.

CHAPTER I.—Standard Guns and their Fabrication Described: Section 1. Hooped Guns; Section 2. Solid Wrought Iron Guns; Section 3. Solid Steel Guns; Section 4. Cast-Iron Guns. **CHAPTER II.**—The Requirements of Guns, Armor: Section 1. The Work to be done; Section 2. Heavy Shot at Low Velocities; Section 3. Small Shot at High Velocities; Section 4. The two Systems Combined; Section 5. Breaching Masonry. **CHAPTER III.**—The Strains and Structure of Guns: Section 1. Resistance to Elastic Pressure; Section 2. The Effects of Vibration; Section 3. The Effects of Heat. **CHAPTER IV.**—Cannon Metals and Processes of Fabrication: Section 1. Elasticity and Ductility; Section 2. Cast-Iron; Section 3. Wrought Iron; Section 4. Steel; Section 5. Bronze; Section 6. Other Alloys. **CHAPTER V.**—Rifling and Projectiles; Standard Forms and Practice Described; Early Experiments; The Centring System; The Compressing System; The Expansion System; Armor Punching Projectiles; Shells for Molten Metal; Competitive Trial of Rifled Guns, 1863; Duty of Rifled Guns: General Uses, Accuracy, Range, Velocity, Strain, Liability of Projectile to Injury; Firing Spherical Shot from Rifled Guns; Material for Armor-Punching Projectiles; Shape of Armor-Punching Projectiles; Capacity and Destructiveness of Shells; Elongated Shot from Smooth Bores; Conclusions; Velocity of Projectiles (Table). **CHAPTER VI.**—Breech-Loading Advantages and Defects of the System; Rapid Firing and Cooling Guns by Machinery; Standard Breech-Loaders Described. Part Second: Experiments against Armor; Account of Experiments from Official Records in Chronological Order. **APPENDIX.**—Report on the Application of Gun-Cotton to Warlike Purposes—British Association, 1863; Manufacture and Experiments in England; Guns Hooped with Initial Tension—History; How Guns Burst, by Wiard, Lyman's Accelerating Gun; Endurance of Parrott and Whitworth Guns at Charleston; Hooping old United States Cast-Iron Guns; Endurance and Accuracy of the Armstrong 600-pounder; Competitive Trials with 7-inch Guns.

Peirce's Analytic Mechanics.

4to. Cloth. \$10.00.

SYSTEM OF ANALYTIC MECHANICS. Physical and Celestial Mechanics. By BENJAMIN PEIRCE, Perkins Professor of Astronomy and Mathematics in Harvard University, and Consulting Astronomer of the American Ephemeris and Nautical Almanac. Developed in four systems of Analytic Mechanics, Celestial Mechanics, Potential Physics, and Analytic Morphology.

"I have re-examined the memoirs of the great geometers, and have striven to consolidate their latest researches and their most exalted forms of thought into a consistent and uniform treatise. If I have hereby succeeded in opening to the students of my country a readier access to these choice jewels of intellect; if their brilliancy is not impaired in this attempt to reset them; if, in their own constellation, they illustrate each other, and concentrate a stronger light upon the names of their discoverers, and, still more, if any gem which I may have presumed to add is not wholly lustreless in the collection, I shall feel that my work has not been in vain." — *Extract from the Preface.*

Burt's Key to Solar Compass.

Second Edition.

Pocket Book Form. Tuck. \$2.50.

KEY TO THE SOLAR COMPASS, and Surveyor's Companion; comprising all the Rules necessary for use in the field; also, Description of the Linear Surveys and Public Land System of the United States, Notes on the Barometer, Suggestions for an outfit for a Survey of four months, etc., etc., etc. By W. A. BURT, U. S. Deputy Surveyor. Second edition.

Chauvenet's Lunar Distances.

8vo. Cloth. \$2.00.

NEW METHOD OF CORRECTING LUNAR DISTANCES, and Improved Method of Finding the Error and Rate of a Chronometer, by equal altitudes. By WM. CHAUVENET, LL.D., Chancellor of Washington University of St. Louis.

Jeffers' Nautical Surveying.

Illustrated with 9 Copperplates and 31 Wood-cut Illustrations. 8vo.
Cloth. \$5.00.

NAUTICAL SURVEYING. By WILLIAM N. JEFFERS, Captain
U. S. Navy.

Many books have been written on each of the subjects treated of in the sixteen chapters of this work; and, to obtain a complete knowledge of geodetic surveying requires a profound study of the whole range of mathematical and physical sciences; but a year of preparation should render any intelligent officer competent to conduct a nautical survey.

CONTENTS.—Chapter I. Formulæ and Constants Useful in Surveying. II. Distinctive Character of Surveys. III. Hydrographic Surveying under Sail; or, Running Survey. IV. Hydrographic Surveying of Boats; or, Harbor Survey. V. Tides—Definition of Tidal Phenomena—Tidal Observations. VI. Measurement of Bases—Appropriate and Direct. VII. Measurement of the Angles of Triangles—Azimuths—Astronomical Bearings. VIII. Corrections to be Applied to the Observed Angles. IX. Levelling—Difference of Level. X. Computation of the Sides of the Triangulation—The Three-point Problem. XI. Determination of the Geodetic Latitudes, Longitudes, and Azimuths, of Points of a Triangulation. XII. Summary of Subjects treated of in preceding Chapters—Examples of Computation by various Formulæ. XIII. Projection of Charts and Plans. XIV. Astronomical Determination of Latitude and Longitude. XV. Magnetic Observations. XVI. Deep Sea Soundings. XVII. Tables for Ascertaining Distances at Sea, and a full Index.

List of Plates.

Plate I. Diagram Illustrative of the Triangulation. II. Specimen Page of Field Book. III. Running Survey of Coast. IV. Example of a Running Survey from Belcher. V. Flying Survey of an Island. VI. Survey of a Shoal. VII. Boat Survey of a River. VIII. Three-Point Problem. IX. Triangulation.

Coffin's Navigation.

Fifth Edition.

12mo. Cloth. \$3.50.

NAVIGATION AND NAUTICAL ASTRONOMY. Prepared for the use of the U. S. Naval Academy. By J. H. C. COFFIN, Prof. of Astronomy, Navigation and Surveying, with 52 wood-cut illustrations.

Clark's Theoretical Navigation.

8vo. Cloth. \$3.00.

THEORETICAL NAVIGATION AND NAUTICAL ASTRONOMY. By LEWIS CLARK, Lieut.-Commander, U. S. Navy. Illustrated with 41 Wood-cuts, including the Vernier.

Prepared for Use at the U. S. Naval Academy.

The Plane Table.

Illustrated. 8vo. Cloth. \$3.00.

ITS USES IN TOPOGRAPHICAL SURVEYING. From the Papers of the U. S. Coast Survey.

This work gives a description of the Plane Table employed at the U. S. Coast Survey Office, and the manner of using it.

Pook on Shipbuilding.

8vo. Cloth. \$5.00.

METHOD OF COMPARING THE LINES AND DRAUGHTING VESSELS PROPELLED BY SAIL OR STEAM, including a Chapter on Laying off on the Mould-Loft Floor. By SAMUEL M. POOK, Naval Constructor. 1 vol., 8vo. With illustrations. Cloth. \$5.00.

Brunnow's Spherical Astronomy.

8vo. Cloth. \$6.50.

SPHERICAL ASTRONOMY. By F. BRUNNOW, Ph. Dr. Translated by the Author from the Second German edition.

Van Buren's Formulas.

8vo. Cloth. \$2.00.

INVESTIGATIONS OF FORMULAS, for the Strength of the Iron Parts of Steam Machinery. By J. D. VAN BUREN, Jr., C. E. Illustrated.

This is an analytical discussion of the formulæ employed by mechanical engineers in determining the rupturing or crippling pressure in the different parts of a machine. The formulæ are founded upon the principle, that the different parts of a machine should be equally strong, and are developed in reference to the ultimate strength of the material in order to leave the choice of a factor of safety to the judgment of the designer. — *Silliman's Journal*.

Joynson on Machine Gearing.

8vo. Cloth. \$2.00.

THE MECHANIC'S AND STUDENT'S GUIDE in the Designing and Construction of General Machine Gearing, as Eccentrics, Screws, Toothed Wheels, etc., and the Drawing of Rectilineal and Curved Surfaces; with Practical Rules and Details. Edited by FRANCIS HERBERT JOYNSON. Illustrated with 18 folded plates.

"The aim of this work is to be a guide to mechanics in the designing and construction of general machine-gearing. This design it well fulfils, being plainly and sensibly written, and profusely illustrated." — *Sunday Times*.

Barnard's Report, Paris Exposition, 1867.

Illustrated. 8vo. Cloth. \$5.00.

REPORT ON MACHINERY AND PROCESSES ON THE INDUSTRIAL ARTS AND APPARATUS OF THE EXACT SCIENCES. By F. A. P. BARNARD, LL.D.—Paris Universal Exposition, 1867.

"We have in this volume the results of Dr. Barnard's study of the Paris Exposition of 1867, in the form of an official Report of the Government. It is the most exhaustive treatise upon modern inventions that has appeared since the Universal Exhibition of 1851, and we doubt if anything equal to it has appeared this century." — *Journal Applied Chemistry*.

Engineering Facts and Figures.

18mo. Cloth. \$2.50 per Volume.

AN ANNUAL REGISTER OF PROGRESS IN MECHANICAL ENGINEERING AND CONSTRUCTION, for the Years 1863-64-65-66-67-68. Fully illustrated. 6 volumes.

Each volume sold separately.

Beckwith's Pottery.

8vo. Paper. 60 cents.

OBSERVATIONS ON THE MATERIALS and Manufacture of Terra-Cotta, Stone-Ware, Fire-Brick, Porcelain and Encaustic Tiles, with Remarks on the Products exhibited at the London International Exhibition, 1871. By ARTHUR BECKWITH, Civil Engineer.

"Everything is noticed in this book which comes under the head of Pottery, from fine porcelain to ordinary brick, and aside from the interest which all take in such manufactures, the work will be of considerable value to followers of the ceramic art."—*Evening Mail*.

Dodd's Dictionary of Manufactures, etc.

12mo. Cloth. \$2.00.

DICTIONARY OF MANUFACTURES, MINING, MACHINERY, AND THE INDUSTRIAL ARTS. By GEORGE DODD.

This work, a small book on a great subject, treats, in alphabetical arrangement, of those numerous matters which come generally within the range of manufactures and the productive arts. The raw materials—animal, vegetable, and mineral—whence the manufactured products are derived, are succinctly noticed in connection with the processes which they undergo, but not as subjects of natural history. The operations of the Mine and the Mill, the Foundry and the Forge, the Factory and the Workshop, are passed under review. The principal machines and engines, tools and apparatus, concerned in manufacturing processes, are briefly described. The scale on which our chief branches of national industry are conducted, in regard to values and quantities, is indicated in various ways.

Stuart's Civil and Military Engineering of America.

8vo. Illustrated. Cloth. \$5.00.

THE CIVIL AND MILITARY ENGINEERS OF AMERICA.

By General CHARLES B. STUART, Author of "Naval Dry Docks of the United States," etc., etc. Embellished with nine finely executed portraits on steel of eminent engineers, and illustrated by engravings of some of the most important and original works constructed in America.

Containing sketches of the Life and Works of Major Andrew Ellicott, James Geddes (with Portrait), Benjamin Wright (with Portrait), Canvass White (with Portrait), David Stanhope Bates, Nathan S. Roberts, Gridley Bryant (with Portrait), General Joseph G. Swift, Jesse L. Williams (with Portrait), Colonel William McRee, Samuel H. Kneass, Captain John Childe with Portrait, Frederick Harbach, Major David Bates Douglas with Portrait, Jonathan Knight, Benjamin H. Latrobe (with Portrait), Colonel Charles Ellet, Jr. (with Portrait), Samuel Forrer, William Stuart Watson, John A. Roebling.

Alexander's Dictionary of Weights and Measures.

8vo. Cloth. \$3.50.

UNIVERSAL DICTIONARY OF WEIGHTS AND MEASURES, Ancient and Modern, reduced to the standards of the United States of America. By J. H. ALEXANDER. New edition. 1 vol.

"As a standard work of reference, this book should be in every library; it is one which we have long wanted, and it will save much trouble and research."—*Scientific American*.

Gouge on Ventilation.

Third Edition Enlarged.

8vo. Cloth. \$2.00.

NEW SYSTEM OF VENTILATION, which has been thoroughly tested under the patronage of many distinguished persons. By HENRY A. GOUGE, with many illustrations.

Saeltzer's Acoustics.

12mo. Cloth. \$2.00.

TREATISE ON ACOUSTICS in Connection with Ventilation.

With a new theory based on an important discovery, of facilitating clear and intelligible sound in any building. By ALEXANDER SÆLTZER.

"A practical and very sound treatise on a subject of great importance to architects, and one to which there has hitherto been entirely too little attention paid. The author's theory is, that, by bestowing proper care upon the point of Acoustics, the requisite ventilation will be obtained, and *vice versa*.—*Brooklyn Union*.

Myer's Manual of Signals.

New Edition. Enlarged.

12mo. 48 Plates full Roan. \$5.00.

MANUAL OF SIGNALS, for the Use of Signal Officers in the Field, and for Military and Naval Students, Military Schools, etc. A new edition, enlarged and illustrated. By Brig.-Gen. ALBERT J. MYER, Chief Signal Officer of the Army, Colonel of the Signal Corps during the War of the Rebellion.

Larrabee's Secret Letter and Telegraph Code.

18mo. Cloth. \$1.00.

CIPHER AND SECRET LETTER AND TELEGRAPHIC CODE, with Hogg's Improvements. The most perfect secret Code ever invented or discovered. Impossible to read without the Key. Invaluable for Secret, Military, Naval, and Diplomatic Service, as well as for Brokers, Bankers, and Merchants. By C. S. LARRABEE, the original inventor of the scheme.

Hunt's Designs for Central Park Gateways.

4to. Cloth. \$5.00.

DESIGNS FOR THE GATEWAYS OF THE SOUTHERN ENTRANCES TO THE CENTRAL PARK. By RICHARD M. HUNT. With a description of the designs.

Pickert and Metcalf's Art of Graining.

1 vol. 4to. Cloth. \$10.00.

THE ART OF GRAINING. How Acquired and How Produced, with description of colors and their application. By CHARLES PICKERT and ABRAHAM METCALF. Beautifully illustrated with 42 tinted plates of the various woods used in interior finishing. Tinted paper.

The authors present here the result of long experience in the practice of this decorative art, and feel confident that they hereby offer to their brother artisans a reliable guide to improvement in the practice of graining.

Portrait Gallery of the War.

60 fine Portraits on Steel. Royal 8vo. Cloth. \$6.00.

PORTRAIT GALLERY OF THE WAR, CIVIL, MILITARY AND NAVAL. A Biographical Record. Edited by FRANK MOORE.

One Law in Nature.

12mo. Cloth. \$1.50.

ONE LAW IN NATURE. By Capt. H. M. LAZELLE, U. S. A. A New Corpuscular Theory, comprehending Unity of Force, Identity of Matter, and its Multiple Atom Constitution, applied to the Physical Affections or Modes of Energy.

Ernst's Manual of Military Engineering.

193 Wood Cuts and 8 Lithographed Plates. 12mo. Cloth. \$5.00.

A MANUAL OF PRACTICAL MILITARY ENGINEERING. Prepared for the use of the Cadets of the U. S. Military Academy, and for Engineer Troops. By Capt. O. H. ERNST, Corps of Engineers, Instructor in Practical Military Engineering, U. S. Military Academy.

Church's Metallurgical Journey.

24 Illustrations. 8vo. Cloth. \$2.00.

NOTES OF A METALLURGICAL JOURNEY IN EUROPE. By JOHN A. CHURCH, Engineer of Mines.

Blake's Precious Metals.

8vo. Cloth. \$2.00.

REPORT UPON THE PRECIOUS METALS: Being Statistical Notices of the principal Gold and Silver producing regions of the World. Represented at the Paris Universal Exposition. By WILLIAM P. BLAKE, Commissioner from the State of California.

Clevenger's Surveying.

Illustrated Pocket Form. Morocco Gilt. \$2.50.

A TREATISE ON THE METHOD OF GOVERNMENT SURVEYING, as prescribed by the United States Congress and Commissioner of the General Land Office. With complete Mathematical, Astronomical and Practical Instructions, for the use of the United States Surveyors in the Field, and Students who contemplate engaging in the business of Public Land Surveying. By S. R. CLEVENGER, U. S. Deputy Surveyor.

"The reputation of the author as a surveyor guarantees an exhaustive treatise on this subject."—*Dakota Register*.

"Surveyors have long needed a text-book of this description.—*The Press*."

Bow on Bracing.

156 Illustrations on Stone. 8vo. Cloth. \$1.50.

A TREATISE ON BRACING, with its application to Bridges and other Structures of Wood or Iron. By ROBERT HENRY BOW, C. E.

Howard's Earthwork Mensuration.

8vo. Illustrated. Cloth., \$1.50.

EARTHWORK MENSURATION ON THE BASIS OF THE PRISMOIDAL FORMULÆ. Containing simple and labor-saving method of obtaining Prismoidal Contents directly from End Areas. Illustrated by Examples, and accompanied by Plain Rules for practical uses. By CONWAY R. HOWARD, Civil Engineer, Richmond, Va.

McAlpine's Modern Engineering.

Second Edition. 8vo. Cloth. \$1.50.

MODERN ENGINEERING. A Lecture delivered at the American Institute in New York. By WILLIAM J. MCALPINE.

Mowbray's Tri-Nitro-Glycerine.


8vo. Cloth. Illustrated. \$3.00.

TRI-NITRO-GLYCERINE, as applied in the Hoosac Tunnel, and to Submarine Blasting, Torpedoes, Quarrying, etc. Being the result of six years' observation and practice during the manufacture of five hundred thousand pounds of this explosive, Mica Blasting Powder, Dynamites; with an account of

THE UNIVERSITY OF MICHIGAN

DATE DUE

DEC 30 1998



SEP 26 2001